



NOTES:

GENERAL NOTES:

Details are indicative and contractor to advise.

Refer to **273/203.0 Fixing details - method statement** for wall panel fixing detail options into existing structure.

Refer to **273/212.0 For poster/print back wall**

All oak surfaces with clear matt lacquer so as to be as natural in appearance as possible. Suggested ref: Envirograf natural lacquer class 0. Contractor to provide samples of all finishes stated for approval prior to manufacture.

QUANTITY REQUIRED:

X3

1/ Solid oak to front edge and sides. Timber junctions to be jointed, e.g. lap or mortise and tenon to be discussed. Also see item 7. Front edge with notches to allow acrylic inserts [item 8] to slot down.

2/ Solid oak front legs, angled as shown. Leg with clear silicon non marking feet. Timber junctions to be jointed, e.g. lap or mortise and tenon to be discussed.

3/ Indicates acrylic line in notched top strut.

4/ Solid oak back legs. Leg with clear silicon non marking feet. Timber junctions to be jointed, e.g. lap or mortise and tenon to be discussed.

5/ Indicates acrylic line in notched top strut.

6/ base to unit in solid oak or mdf with oak veneer. Note recessed area for posters to rest. Also note notching to correspond with top notches for acrylic dividers to fit into.

7/ Back top edge is of solid oak with recess for postcard display. Recess with laminate finish to base. Edge with notches to allow acrylic inserts [item 8] to slot down. Postions optional. Laminate Ref: **Abet Laminati Print S802 (478) SE1 Colorpact**. Laminate to be fixed according to manufacturers instructions

8/ Clear acrylic dividers to be provided fitted to slotted unit. Suggest 6mm acrylic with bullnose radius to top corners as shown.

9/ 6mm clear acrylic top to be provided fitted to recess and to cover postcard display. Top with notches to allow finger grip for ease of removal.

GENERAL NOTES:

DO NOT SCALE FROM THIS DRAWING. REFER TO WRITTEN DIMENSIONS ONLY. ALL DIMENSIONS AND LEVELS TO BE CHECKED ON SITE BY THE CONTRACTOR PRIOR TO COMMENCEMENT OF WORKS. ANY DISCREPANCIES TO BE REPORTED TO THE DESIGNER IMMEDIATELY AND PRIOR TO COMMENCEMENT OF WORKS.

ALL DRAWINGS TO BE READ IN CONJUNCTION WITH WRITTEN SPECIFICATIONS / ASSOCIATED DOCUMENTATION SUPPLIED BY THE DESIGNER.

THIS DRAWING SHOWS THE DESIGN INTENT ONLY. THE CONTRACTOR SHALL ADVISE ON ALL DETAILS AND ENSURE STRENGTH AND STABILITY IN ALL CONSTRUCTION.

THE CONTRACTOR TO PROVIDE SETTING OUT AND ROD DRAWINGS FOR APPROVAL PRIOR TO CONSTRUCTION.

ALL SERVICES TO COMPLY WITH LOCAL AUTHORITY, BUILDING CONTROL AND ENVIRONMENTAL HEALTH REQUIREMENTS AND TO SERVICES ENGINEERS DETAILS.

ALL STRUCTURE TO LOCAL AUTHORITY AND BUILDING CONTROL REQUIREMENTS AND TO STRUCTURAL ENGINEERS DETAILS AND CALCULATIONS.

DO NOT SCALE THIS DRAWING. CHECK ALL DIMENSIONS ON SITE

THE CONTRACTOR SHALL COMPLY WITH:
CDM REGULATIONS 2007

FIRE PRECAUTIONS:
CODE OF PRACTICE FOR THE PREVENTION OF FIRES ON CONSTRUCTION SITES AND BUILDINGS UNDERGOING REFURBISHMENT

ALL CONSTRUCTION AND MATERIALS TO CONFORM TO CURRENT BUILDING AND FIRE REGULATIONS.

SITE WASTE MANAGEMENT:
THE CONTRACTOR SHALL MANAGE ALL WASTE MATERIALS AND RE-USE / RECYCLE AS MUCH AS POSSIBLE TO MINIMISE WASTE.

RISK ASSESSMENT:
THE CONTRACTOR MUST ENSURE THAT THE SITE IS A HAZARD FREE ENVIRONMENT AT ALL TIMES.
STANDARD SAFETY CLOTHING AND EQUIPMENT MUST BE WORN AT ALL TIMES.
THE CONTRACTOR MUST EMPHASISE POTENTIAL SITE RISKS AND HAZARD TO ALL OPERATIVES ESPECIALLY DURING DEMOLITIONS AND STRUCTURAL WORKS.

IF IN DOUBT - ASK THE DESIGNER

DRAWING STATUS: **FOR TENDER**

REVISIONS:

--

CLIENT: **CHURCHILL WAR ROOMS**

PROJECT: **CWR Shop**

PROJECT ADDRESS:
**King Charles Street
London SW1A 2AQ**

DRAWING TITLE **Perimeter poster unit**

SCALE **As shown** PAPER SIZE **A3**

DRAWN BY **CJ** DATE **Sept 2015**

PROJECT NUMBER **273**

DRAWING NUMBER **273/211.0** REVISION **-**