

MBA CONSULTING

MultiREBAR Schedule ref:

24060/52

01

Rev.
A

Site ref: PENZANCE DRY DOCK
WHARF ROAD,
PENZANCE.

Date prepared: OCT.'24

Date revised:

Location: R.C. DETAILS ON PILE CAPS.
Job No: 24060

Prepared By: DAF

Checked by: GM

Member	Bar mark	Type & size	No of mbrs	No of bars in each	Total no	Length of each bar † mm	Shape code	A mm *	B mm *	C mm *	D mm *	E/R mm *
R.C. Details on	01	H 20	7	3	21	2325	21	625	1175	(625)		
Triple Pilecap's.	02	H 10	7	3	21	1750	21	300	1175	(300)		
	03	H 20	7	3	21	2225	21	625	1075	(625)		
	04	H 10	7	3	21	1650	21	300	1075	(300)		
	05	H 20	7	1	7	2175	21	625	1035	(625)		
	06	H 10	7	1	7	1600	21	300	1035	(300)		
	07	H 20	7	1	7	1950	21	625	810	(625)		
	08	H 10	7	1	7	1375	21	300	810	(300)		
	09	H 20	7	1	7	1725	21	625	575	(625)		
	10	H 10	7	1	7	1150	21	300	575	(300)		
	11	H 20	7	2	14	2100	21	625	955	(625)		
	12	H 10	7	2	14	1525	21	300	955	(300)		
	13	H 20	7	2	14	1775	21	625	635	(625)		
	14	H 10	7	2	14	1200	21	300	635	(300)		
	15	H 10	7	6	42	1800	27	535	485	(780)	280	
	16	H 10	7	3	21	1575	25	535	535	465	465	(495)
R.C. Details on	01	H 20	33	4	132	2325	21	625	1175	(625)		
Double Pilecap's.	02	H 10	33	4	132	1750	21	300	1175	(300)		
	17	H 10	33	7	231	2450	51	660	475	130	(130)	
R.C. Details on	18	H 20	20	8	160	1025	21	275	575	(275)		
Single Pilecap's.	19	H 10	20	8	160	1100	21	275	575	(275)		