


Legend:

- W INCOMING MAINS COLD WATER
- MAINS COLD WATER
- INCOMING ELECTRICITY SERVICE
- BT INCOMING DATA DUCTS
- ES MIRA ADVANCE FLEX EXTRA ELECTRIC SHOWER
- FAP FIRE ALARM PANEL
- WH HEATREA SADIA 15ltr HOTFLO UNVENTED ELECTRIC WATER HEATER
- W WATER METER
- WSM WATER SUB METER
- BT BT POINT
- E ELECTRICITY METER
- DISTRIBUTION BOARD
- ELECTRIC RADIATOR
- ER 1 DIMPLEX PLXE PANEL HEATER 430mm X 860mm (2.00 kW)
- ER 2 DIMPLEX PLXE PANEL HEATER 430MM X 690MM (1.25 KW)
- STOPCOCK
- 6U WALL MOUNTED DATA CABINET
- L1E IP65 RATED WHITECROFT MIRAGE RECESSED DOWNLIGHTER WITH INTEGRAL 3hr EMERGENCY LUMINAIRE CAPABILITY
- L2E IP65 RATED WHITECROFT SPECTRE WX WALL MOUNTED BULKHEAD DOWNLIGHTER WITH INTEGRAL 3hr EMERGENCY LUMINAIRE CAPABILITY

Notes:

- THIS DRAWING SHALL BE READ IN CONJUNCTION WITH ALL OTHER DRAWINGS, SPECIFICATIONS, SCHEDULES AND BUILDING MODELS INCLUDING SCHEMATICS. THE CONTRACTOR SHALL REFER TO THE ARCHITECTS DRAWINGS FOR SETTING OUT DETAILS/DIMENSIONS.
- THE MECHANICAL AND ELECTRICAL SERVICES INSTALLATIONS ARE DESIGNED TO COMPLY FULLY WITH THE BUILDING REGULATIONS STANDARDS, AND ARE DESIGNED IN ACCORDANCE WITH THE RECOMMENDATIONS OF THE CIRSE GUIDES, AS ISSUED BY THE CHARTERED INSTITUTION OF BUILDING SERVICES ENGINEERS.
- REFER TO THE ARCHITECTS DRAWINGS FOR DETAILS OF ALL BUILDING FIRE COMPARTMENTATION BARRIERS. ANY SERVICES PENETRATING THE FIRE COMPARTMENT SHALL BE FIRE SEALED USING THE APPROVED PENETRATION DETAIL.
- ALL PENETRATIONS THROUGH FIRE WALLS SHALL BE FIRE STOPPED TO MAINTAIN THE FIRE INTEGRITY OF THE FIRE WALL. ALL SLAB PENETRATIONS TO HAVE FIRE STOPPING TO MAINTAIN THE INTEGRITY OF THE FIRE RATED SLAB. THE CONTRACTOR SHALL MAKE GOOD ALL PENETRATIONS TO THE APPROVAL OF BUILDING CONTROL.
- THIS DRAWING SHALL NOT BE USED FOR INSTALLATION. THE MECHANICAL AND ELECTRICAL SERVICES CONTRACTORS SHALL BE RESPONSIBLE FOR PRODUCTION OF COORDINATED INSTALLATION DRAWINGS CHECKED WITH ACTUAL SITE DIMENSIONS.
- ALL DIMENSIONS WHERE INDICATED ARE IN MILLIMETRES UNLESS STATED OTHERWISE. ALL DIMENSIONS SHALL BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF ANY WORKS.
- ALL PIPES AND CABLES TO BE WITHIN VOIDS UNLESS OTHERWISE STATED.




SWITCHED VIA 5+2  
TIMECLOCK AND PHOTOCELL

PV INVERTER  
100A 8 WAY TYPE B MAIN PANEL BOARD DIMENSIONS:  
HEIGHT:564mm  
WIDTH:440mm  
DEPTH:130mm  
INCOMING WPD

INCOMING SERVICES SCHEDULE

WATER	32Ø MDPE, 2.0Ltrs/s METERED BRANCH FROM SOUTH WEST WATER
ELECTRICITY	100A 3-PHASE (69kVa) METERS SERVICE FROM WPD
BT	2No. DUCTS AND MANHOLES FREE ISSUED FROM BT OPEN REACH



STANDARD TRENCH DETAIL

ALL SERVICES SHALL BE LAID ON AT LEAST 100mm BEDDING MATERIAL AND INCLUDE MARKER TAPES ABOVE

THIS DRAWING IS NOT TO BE USED FOR CONSTRUCTION. INSTALLATION DRAWINGS SHOULD BE PRODUCED BY THE CONTRACTOR AND AGREED WITH THE CLIENT TEAM PRIOR TO ANY INSTALLATION WORK

THIS DRAWING SHALL BE PRINTED IN COLOUR

Rev	Date	By	Chk	Aprvd	Description
-----	------	----	-----	-------	-------------

PROJECT  
Liskeard CLLD Scheme

CLIENT



www.methodllp.com Swindon Tel: 01793 822044

DRAWING TITLE  
Combined M&E Layout  
Ground Floor

SUITABILITY  
S2 - FOR INFORMATION

DATE	SCALE	DRWN BY	CHK BY	APVD BY
19.03.21	1:50 - A1	LMS	LXJ	NJS

DRAWING NUMBER	REVISION No.
1631MLC-MET-00-DR-M-9001	S2 - P01

Scaling Note: Do NOT scale from this drawing.