

Appendix 8 – Hard Landscaping Services Scenarios

Scenario 1

To remove existing mortar between the cobbles to a depth of 50mm and replace with a black strong mortar for a section 20 m long. Cost to include all materials, plant and equipment.

Scenario 2

Uplift 80m² of existing ACC granite paving, pallet the uplifted paving onto free issue pallets keeping the sizes different sized flags separated. Relay the 80m² area with new ECL paving which is 4 different colourer reconstituted stone. Cost to include all materials, plant and equipment.

Scenario 3

Uplift 20 m² of existing paving which has sunk due to vehicular movement. Re bed base layer, compact and relay paving back to original levels. Cost to include all materials, plant and equipment.

Scenario 4

A man hold has sunk, distorting the paving levels around it, quote to uplift 10m² repair top section on man hole bedding in a new paved lid from. Relay existing paving to original levels. Cost to include all materials, plant and equipment.