

Construction of new Changing Rooms at Cliffe Memorial Hall, Cliffe, Rochester, Kent

Brief Specification

The be read with drawing no's C104.1,10B & 11.

Allow the sum of £10,000.00 for contingencies.

All the P.C. sum of £650.00 per thousand stock facing bricks

Roof tiles to be Redland DuoPlain interlocking tile

Sanitary Fittings

Armitage Sanks 'M' pack for all toilets

Siruis thermostat showers

Allow the P.C. sum of £2,000.00 for rapid electric hot water cylinder

Allow the P.C. sum of £15.00 per m² for floor tiles

Electric installation

Provide light fittings to give 600 Lux at floor level

Provide 3no. double gang 13amp sockets to each changing room

Provide linked smoke detectors to each changing room with 4 hour battery backup.

Allow the P.C. sum of £3,000.00 for external paths_