

ROOM DATA

FINISHES

- Floor Vinyl sheet covering to kitchen
- Wall Replacement carpet to meeting room
- Wall Painted plasterboard and skim, 2 rows of tiles above kitchen units - as existing.
- Ceiling Painted plasterboard and skim
- Acoustic ceiling above meeting room, kitchenette and store to be set below the existing beams.
- Joinery Painted architrave and skirting to match existing. Client to advise if any patressing required within the new partition for fixing of heavy items.

VENTILATION

As existing to meeting room - window to be eased and adjusted to ensure it is operable. Extract vent to kitchen.

FIXTURES AND FITTINGS

Kitchen fittings to have white doors and laminate worktop. To include under counter fridge and sink. Space for countertop microwave and tea urn (to be provided by client). Water heater.

ELECTRICS


Additional double power socket in the meeting room for the projector. Sockets as necessary to kitchen including 2 x double sockets above worktop level. Heating loop in meeting room - there is one currently, but this will need to be moved when the ceiling is installed. Projector and retractable screen in meeting room - client supply. Ceiling mounted LED lighting strips.

HEATING

Electric underfloor heating to wc. Existing Radiators to meeting room and to corridor spaces.

In existing corridor / new stairs:

Vinyl sheet flooring similar to existing. New double socket near the fire extinguisher location on the Reading Room wall.



HIGH PEAK ARCHITECTS LTD

2nd Floor, Wharf House, Wharf Road, Whaley Bridge, High Peak, Derbyshire SK23 7AD
Tel: 01663 719717 Website: highpeakarch.com Email: hpa@highpeakarch.com

Remodel and lift

Ground floor Kitchen & meeting room

Mechanics Institute, Whaley Bridge

1866.BR06

Rev B 5 September 2024

ISSUED FOR TENDER

Rev A 8 February 2024

General revisions

Scale: 1:20 @ A2

Date: November 2023

DO NOT SCALE OFF THIS DRAWING

Rev: B