

# GENERAL

These notes to be read in conjunction with detailed specification from Burnley Council.

Any discrepancies are to be reported to any supervising officer and Burnley Council.

All workmanship and materials to comply with current Building Regulations and relevant British Standards, Codes of Practices. All electrical work to conform to current edition of IEE regs and to be carried out by part P approved contractor.

Any gas related works to be carried out by gas safe registered contractor. All materials to be fixed, applied or mixed in accordance with manufacturer's instructions and specifications.

The contractor shall take into account everything necessary for the proper execution of the works.

All dimensions to be checked on site by the contractor prior to ordering of any materials and any discrepancies brought to the

attention of the client. All work to be carried out in accordance with CDM regulations 2015 and Health & Safety at work act.

Strip out all plumbing and heating and provide and fix new hot and cold water pipework, wastes, sup etc to new bathroom and kitchen. Provide and fix new class A rated gas fired boiler with fan assisted flue to kitchen fixed in accordance with manufactures instructions, TRV's to new radiators

Provide and fix new kitchen units as per schedule.

New bathroom suite with deep seal anti vac traps to wastes to connect to new soil and vent pipe. Include for shower over the bath, all tiling and shower screen etc.

100mm drainage laid to falls 1:40 to manufacturers instructions and runs agreed and inspected by Building Control Officer

Remove existing partitions, any new partitions required to be 100 x 50mm timber studding with acoustic insulation, 9mm plasterboard both sides and skim finish.

Provide extra noggings in floor as necessary. Include for new doors complete with new frames, architraves, skirtings etc

Remove / overboard ceilings with 12.5mm plasterboard and skim ceilings to rooms indicated on schedule, provide 2 layers 200mm rockwool insulation laid in opposite directions to rootspace and new insulated costs hatch.

Remove plasterwork to walls as indicated on schedule, external walls lined out with Thermaline super board and party walls with soundbloc boards with skim finish.

Provide new dpc to all ground floor walls including waterproof render / tanking prior to dry lining

**Proposed First Floor Plan** 

Strip out and rewire property to points shown, all electrical work to conform to current edition of IEE regs and to be carried out by part P approved contractor. Include for new security alarm

svp

wardrobes

cyl cupb'd

SD 🥢

rear bedroom

wardrobes

resite

20

Kitchen mechanical extract ventilation to achieve 30 litres/second adjacent to a hob or 60 litres/second elsewho

Bathroom / shower fan to have 15 minutes overrun and to operate via the light switch Smoke / heat detectors to be mains wired with battery back up and interlinked

# ELECTRICAL SYMBOLS

 $\begin{picture}(60,0)\put(0,0){\line(1,0){100}} \put(0,0){\line(1,0){100}} \put(0,0){\line(1,0){100}$ 

13 amp low level double switched sockets

FS 🖵 Fused outlet (boiler etc)


High level switch with neon indicator and socket below

Cooker control unit complete with socket

Light switch one way 2 Light switch two way Pull switch



 $igorplus ag{TV socket}$ Alarm keypad



External wall light



### Amendment A 24th Aug 2023, kitchen layout updated

### Project

flat roof to kitchen

bathroom run above f

around waste pipes

extract taken

through roof

shower ove

0

bathroom

form cupb'd

front bedroom

to soil and vent pipe, form

new partition to party wall to conseal wastes, include for acoustic insulation

new waste run above rear bedroom floor and flat roof to soil and vent pipe

#### **Alterations / Refurbishment** 16 Hornby Street, BURNLEY

### Client

# Burnley Borough Council

Description		Drawn
Proposed Plans		cw
Scale	Date	Drawing No
1:50 @ A3	Aug 2023	638/02A