



| TASK NO. | TASK/DESCRIPTION | NOTES |
|----------|---|-------|
| | H9 MISCELLANEOUS | |
| H9.01 | <div><p>Anti Bird Netting</p><p>Anti-bird netting is fitted to port and stbd shade decks and quarterdeck. Current netting is in poor condition and is no longer preventing birds from perching. RENEW anti-bird netting on shade decks with equivalent to current fitting. Quarterdeck anti-bird netting must be fireproof for 3m in all directions from quarterdeck access door due to flashover from door frame during door breaching exercises.</p><p>ALLOW for approximately 150m x 3m RENEWAL.</p></div> | |

| TASK NO. | TASK/DESCRIPTION | NOTES |
|----------|---|--|
| | H9 MISCELLANEOUS | |
| H9.02 | <p>Toilet Block and Staff Office</p>  | To be completed in conjunction with H2.17 and H2.18. |



Currently 2 office units and 1 toilet unit fitted. Contractor to remove and dispose of existing units and supply and fit replacements (only 1 office unit required along with toilet unit).


Craneage will be required to remove existing and replace with new.

Current toilet block contains 3 x urinals, 3 x toilets and 3 x wash basins.

Existing unit dimensions(m) – Toilet block 2.75w x 3.6d x 2.6h

Office Block 12.3w x 3.7d x 2.6h

Office unit to contain changing area and kitchen area as per existing unit.

| TASK NO. | TASK/DESCRIPTION | NOTES |
|----------|--|-------|
| | H9 MISCELLANEOUS | |
| H9.03 | <p>Gundeck Redundant Aerials</p>  <p>There are five in number redundant aerials fitted on the gundeck. Two aerials have already had their mountings so weakened by corrosion that they have come detached, therefore to avoid injury or damage in the future the five remaining aerials are to be REMOVED and disposed of by Contractor.</p> | |

| TASK NO. | TASK/DESCRIPTION | NOTES |
|----------|---|--|
| | H9 MISCELLANEOUS | |
| H9.04 | <p>Ballast Tank</p> <p>One in number ballast tank requires topping up with fresh water. Contractor is to complete this task and provide the volume of water required to the Authorised Overseer to record in ships Stability records.</p> <p>ALLOW for 500m³ fresh water.</p> | <p>Ballast tank will be identified to contractor prior to RPSD</p> |