

Price List

Name	570127 A303 Cheshay’s Hill WB MP224/0 Ground Investigation
Contractor	[Contractor to state name]

Guidance notes & preamble for the Contractor

The Contractor is paid in accordance with Clause 50 & 51. The rates and prices entered in the Price List shall be deemed to be the full inclusive value of the work covered by the items

You are required to submit a Rate or Price for each Item associated with the Providing the Works

Where an Item has specified Quantity, you should enter a value in the Rate column and the Price for each Item should be equal to the specified Quantity multiplied by your submitted Rate. Payment for these items will be made in accordance with the Contract i.e. total Quantity completed multiplied by the Rate.

For Items where the unit is specified as 'lump sum' you should submit a Price only.

All Rates and Prices must be quoted in pounds and whole new pence to two decimal places and exclude VAT. Any item priced as zero must be explained.

You should ensure the total is correct before submission. If necessary, the Employer may contact a tenderer whose Offer has required an arithmetical adjustment.

Price List Part 2

Item No.	Item Description	Unit	Quantity	Rate	Price
A1	Establish on site all plant, equipment and services for a Green Category site	lump sum		£0.00	£0.00
A2	Provision of NHSS 18 accredited grass cutting/trimming crew to clear area of trial pits and stockpiles	day	1		
A3	Provide professional attendance in accordance with Clause 3.5.2	lump sum		£0.00	£0.00
A4	Establish the location and elevation of the ground at each exploratory hole	lump sum		£0.00	£0.00
A5	Preparation of Health and Safety documentation and Safety Risk Assessment.	lump sum		£0.00	£0.00

Item No.	Item Description	Unit	Quantity	Rate	Price
A6	Digital data in AGS transfer format	lump sum		£0.00	£0.00
A7	Determination of EWC code in accordance with Technical Guidance WM3	lump sum		£0.00	£0.00
A8	One master copy of the Factual Report (or specified part thereof) in PDF and HA toolkit format	lump sum		£0.00	£0.00
A9	Provision of excavation plant and crew for machine dug trial pits on a slope of gradient greater than 20% including standing time for groundwater strikes and undertaking of in-situ testing.	day	5	£0.00	£0.00
A10	Extra over A8 for the provision, installation and removal of track mats and other protective measures required at each trial pit location	day	5	£0.00	£0.00
A11	Small disturbed sample	nr	30	£0.00	£0.00
A12	Bulk disturbed sample	nr	15	£0.00	£0.00
A13	Provision of containers and collection of samples for contamination Suite L	nr	5	£0.00	£0.00
A14	Hand vane test (set of 3 peak and 3 residual strength readings)	nr	30	£0.00	£0.00

Item No.	Item Description	Unit	Quantity	Rate	Price
A15	Undertake laboratory testing - Water content	nr	15	£0.00	£0.00
A16	Undertake laboratory testing - Liquid limit, plastic limit and plasticity index	nr	15	£0.00	£0.00
A17	Undertake laboratory testing - Particle size distribution by wet sieving	nr	10	£0.00	£0.00
A18	Undertake laboratory testing - shear strength of a set of 3 60mm x 60mm square specimens by direct shear, test duration not exceeding 3 days per specimen.	nr	9	£0.00	£0.00
A19	Extra over for sample preparation including screening, mixing to natural moisture content and remoulding.	nr	9	£0.00	£0.00
A20	Undertake laboratory testing - Suite B (greenfield site - pyrite present)	nr	4	£0.00	£0.00
A21	Undertake laboratory testing - Suite L including assessment of EWC code	nr	8	£0.00	£0.00
					£0.00