



AD 979

Amesbury Town Council

The Bowman Centre, Shears Drive, Amesbury, Wilts, SP4 7XT

Telephone 01980 622999

Email: townclerk@amesburytowncouncil.gov.uk



AD 979

PLAY AREA ENHANCEMENT 2021

CONTRACT BRIEF: DESCRIPTION OF WORKS

SCHEME NAME: Play Park Enhancement
Detailed requirements of scheme
Bonnymead Park
1. Hopscotch panel: - remove existing paint and thoroughly clean surface. - repaint hopscotch game in a variety of hard wearing / weather proof / non slip paints.
2. Revolve Roundabout: - remove existing unit and footings, dispose off site. - remove existing wet pour and sub-base as necessary. - supply and install 1 x inclusive roundabout. - supply and install sub-base and wetpour around inclusive roundabout, up to existing surrounding kerb stones.
3. Double gate - fill sunken hole underneath double gates with wetpour, including any necessary sub-base.
4. Springie - remove missing units existing footings and dispose off site. - remove existing wet pour and sub-base as necessary. - supply and install 1 x hardwearing (damage proof) sit-on springie. - supply and install sub-base and wetpour around new and exiting springee's, up to existing surrounding kerb stones.
5. Swings - remove existing sub-base and wetpour underneath unit - replace sub-base and wetpour, around unit, up to existing surrounding kerb stones.
6. Basket Swing - remove existing sub-base and wetpour underneath unit . - replace sub-base and wetpour,, around unit, up to existing surrounding kerb stones.
7. Multi-play unit - remove existing sub-base and wetpour underneath unit. - replace sub-base and wetpour, around unit, up to existing surrounding kerb stones
8. Large multi-play unit - remove existing sub-base and wetpour underneath unit - replace sub-base and wetpour, around unit, up to existing surrounding kerb stones. (taking care not to disturb the tube underneath for the talking panels)
9. See-saw - remove existing sub-base and wetpour underneath unit

- replace sub-base and wetpour,, around unit, up to existing surrounding kerb stones.
10. Tyre Swing
- remove existing sub-base and wetpour underneath unit
- replace sub-base and wetpour,, around unit, up to existing surrounding kerb stones.
Harvard Park Toddler
Wetpour
- remove existing sub-base and wetpour
- replace sub-base and wetpour, around existing play equipment, up to existing surrounding kerb stones.
Harvard Park Teenager
Surface
- supply and install paver grid system underneath 4 picnic benches so that it is level and flat. Paver grids to be installed flush with ground level.
- supply, install and compact soil on top of paver grid.
Surface
- supply and install top soil with grass seed to fill in dips by 2 x goals. Compact soil as necessary
Whelan Way
Surface
- remove existing tiles and sub-base
- replace sub-base and wetpour around individual units and install kerb stones at edge.
Notes
- wetpour underneath equipment within all play park are to be one solid colour.
Additional Items
- temporary security fencing hire
- post inspection installation
- hire of welfare & storage facilities
- leave all sites clean and tidy, removing all arisings
<p>Amesbury Town Council Bowman Centre, Shears Drive, Amesbury, Wiltshire SP4 7XT admin@amesburytowncouncil.gov.uk 01980 622999</p>