


Installation.

Supply and install double glazed windows comprising:-

1. Sealed double glazed units with not less than 4mm laminated glass to comply with all BR and BS standards.
2. All units to have thermal resistance to comply with current Building Regulations Approved Document L.
3. All frames to be constructed of robust, heavy duty aluminium, galvanised and finished in polyester powder coating in white to match the existing color on site.
4. All frames to be a minimum of 40mm width and high security.
5. All opening lights are to be top hung.
6. All windows to incorporate:-
 - A minimum of 2No. Strand Duoflex folding openers with connecting bar (or similar to be approved by Dave Clayton) finished in satin stainless steel.
 - Frames to incorporate background ventilation to comply with all current Approved Document Building Regulations.
 - Hinges to be high security and are not to be visible externally when closed.
 - All glazing beading to be internal.
 - All external cills to be robust aluminium and incorporate bottom drip.
7. The contractor is responsible for making good.
8. All glazing is to be safety glass and is to be kite marked.
9. The contractor is responsible for providing all access to all windows.



NOTES:
 1. DO NOT SCALE FROM DRAWING.
 2. ALL DIMENSIONS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORKS.
 3. THIS DRAWING IS COPYRIGHT TO LEICESTERSHIRE FIRE AND RESCUE.
 4. PERSONNEL SHOULD NOTE RELEVANT ITEMS REGARDING THE CONDITION OF THE EXISTING STRUCTURE CONTAINED WITHIN THE HEALTH & SAFETY FILE SHOULD THIS BE AVAILABLE



?	
REVISIONS	

LEICESTERSHIRE FIRE and RESCUE SERVICE		Estates Department Leicestershire Fire and Rescue Headquarters 12 Geoff Monk Way Birstall Leicestershire LE4 3BU
PROJECT NUMBER		
PROJECT TITLE	Lutterworth Fire & Rescue Station	

TITLE
 Extension Project
 Proposed Windows

DRAWING No	REV	SCALE
DC/P/LUT/2017/112		1:10@A2
DRAWN BY	DATE	
DC	10/12/2017	
CHECKED BY	SIZE/PLOT	
	A2	
ACAD FILE	UERN	