

### Health and safety

A risk assessment, method statement and proof of employer's liability and public liability insurance will be required before work commences on site. (£5 million Public Liability and £10 million Employer's Liability Insurance for each and every claim required). The existing tennis courts can be closed while the works are carried out. Individual areas of work may require security fencing protection to protect areas of excavation from unauthorised access to the area from the public. The successful tenderer will be required to develop the construction phase health & safety plan further and submit it to the client for approval before work commences.

### Timing

Work is planned for the end of January, beginning of February, 2022. The work will be in 2 phases, with phase 1 being the removal of the existing tennis court chain link fencing. Phase 2 will be required approximately 2 weeks later and will include the site clearance, access improvements and the installation of the perimeter weld mesh fencing around the tennis court and also the new tennis net installed. It is expected that the successful tenderer will have ordered all necessary materials such as the new 2m high weld mesh fence and tennis nets in order that the works can be completed within the suggested time frame. Reinstatement will be required upon completion of the work and a photographic record will be kept by the client prior to the works as a point of reference.

### Multi-use Games Area

The supply and installation of a 18 x 30m Multi-Use Games Area (MUGA) has been ordered by the client.

- Supply and installation of a 18 x 30m multi-use games area has been ordered with Steelway Fensecure and expected to be installed late Jan- early Feb. Phase 1 of the works ie the removal of the old chain link fencing will be required prior to the MUGA being installed, and as such some flexibility is requested to work within the timeframe set by the MUGA installation.

### T & C's

The Council's usual terms and conditions would apply and are attached. A standard hard and soft works specification is attached and would apply.

### Disposal of arisings

All arisings should be removed from site to a registered recycling plant or registered waste disposal centre. A waste carriers licence should be in possession to allow this and will be requested for inspection as part of the review of submitted H & S information.

### Access

Lowerfold Park is located in Great Harwood BB6 7NS. The tenderer should familiarise themselves with the site prior to providing a quote. Some photos of the area are attached for reference only.