



LEGEND:

- HIGH VISIBILITY NETTING:** secured to road pins / pig tails to identify edges or root protection areas.
 - CABLE TRENCH:** electrical cable trench 500mm wide, 675mm depth to receive 50mm armoured electrical cable and surface made good to match existing as details 5, 6 & 7.
 - HAND DUG CABLE TRENCH:** electrical cable trench 300mm wide, 175 - 475mm depth within RPA to be hand dug to receive 50mm armoured electrical cable (& CAT 5 cable were required) and surface made good to match existing as detail 8.
 - ROOT PROTECTION AREA:** minimum area to be protected during construction in accordance with BS 5837:2012.
- ARBORICULTURAL METHOD STATEMENT:** refer to the Arboricultural Method Statement 19135 / EH / AMS001 for more detailed information.

This drawing and the design it depicts are copyright and may not be copied or reproduced without written permission from Beo Landscape Design Ltd. No liability will be accepted for amendments made by others. This drawing is to be read in conjunction with the landscape specification and other relevant drawings.

Contains Ordnance Survey Data © Crown Copyright and Database Right 2020. © Crown Copyright. All rights reserved 100018739.

Refer any query to office of origination.

rev	date:	amendments:	all:
A	21/09/20	Ground marker locations amended.	E.H
B	23/10/20	Ground light locations amended.	E.H
C	28/10/20	Legend amended.	E.H

cdm 2015: designers residual risk information

In addition to the risks & hazards normally associated with the type of work detailed on this drawing the following residual risks should be noted:

- Construction:**
1. Changes in level across the site including ramped access / steps.
 2. The proximity of adjacent pavements, estate roads & car parks.
 3. The proximity of adjacent buildings and buried associated services.

- Maintenance:**
1. Changes in level across the site including ramped access / steps.
 2. The proximity of adjacent pavements, estate roads & car parks.
 3. The proximity of adjacent buildings and buried associated services.

It is assumed that works will be carried out by competent contractor working where appropriate to an approved method statement.



client: COMPTON VERNEY HOUSE TRUST

project: GROUNDS LIGHTING COMPTON VERNEY

title: TREE PROTECTION PLAN ZONE 1 & 2

status: TENDER

date: JUL'20	drawn: E.C.H	number: 19-135-08
scale@A1: 1:100	checked: T.G-W	revision: C

Beo Landscape Design Ltd
132A 'The Westlands', Compton Road, Wolverhampton, WV3 9GB
T: 01902 424 950 / 01902 425 001
E: info@beolandscape.co.uk
W: www.beolandscape.co.uk

