



Pipes will continue along the concrete as outlined below and enter the plant room

Water feed (Blue) will be ran in Galvanised steel piping and clipped to the underside of the soffit

Services are to be ran up the concrete wall in this location

Electrical cable (red) will be ran in White PVC conduit clipped to the underside of the concrete soffit

Orange line denotes the top of the stud wall

Services are to be ran inside of the the timber stud wall once entering from the top