

Project: Leicestershire Fire & Rescue Service - USAR Training Facility

Project

Name: Leicestershire Fire & Rescue Service – USAR Training Facility

Address: 12 Geoff Monk Way, Birstall, Leicester. LE4 3BU

Client: Leicestershire Fire & Rescue Service

Shape Codes According to: BS 8666:2005

Rebar Weight Schedule

	Number of Bars	Total Weight [kg]
TOTALS	179	266.29 kg

Rebar Bending Schedule

Member	Bar Mark	Type + Size	Total No.	Length of each bar [mm]	Shape Code	A [mm]	B [mm]	C [mm]	D [mm]	E / R [mm]	Rev
	01	H12 mm	8	1405	51	335	245	160	160		
	02	H12 mm	28	1140	51	345	120	145	160		
	03	H12 mm	22	1670	21	800	120	800			
	04	H12 mm	28	2400	00	2400					
	05	H12 mm	8	1450	00	1450					

Project: Leicestershire Fire & Rescue Service - USAR Training Facility

Member	Bar Mark	Type + Size	Total No.	Length of each bar [mm]	Shape Code	A [mm]	B [mm]	C [mm]	D [mm]	E / R [mm]	Rev
	06	H12 mm	4	2080	51	815	120	145	160		
	07	H12 mm	16	850	00	850					
	08	H12 mm	4	1290	51	420	120	145	160		
	09	H12 mm	4	885	51	220	120	145	160		
	10	H12 mm	1	2810	21	1320	220	1320			
	11	H12 mm	18	1040	33	320	95	145		155	
	12	H12 mm	34	2475	13	1220	95	1220			
	13	H12 mm	4	1235	13	600	95	600			

Project: Leicestershire Fire & Rescue Service - USAR Training Facility

Member	Bar Mark	Type + Size	Total No.	Length of each bar [mm]	Shape Code	A [mm]	B [mm]	C [mm]	D [mm]	E / R [mm]	Rev
											