

TASK NO.	TASK/DESCRIPTION	NOTES
	H8 INTERNAL DECKS, DOORS AND LADDERS	
H8.04	<p data-bbox="411 389 1062 421">Stbd Troop Accommodation Compartment Deck</p> <div data-bbox="408 443 1166 808">  </div> <p data-bbox="411 824 1214 936">Following a compartment flood, the deck screed has broken down in certain areas. Damaged screed to be removed to SURVEY steel deck below. Compartment requires confirmed dry (possible dehumidifiers required) with screed RENEWED and REPRESENTED on completion.</p> <p data-bbox="411 969 1214 1025">ALLOW for 6m² screed RENEWAL. ALLOW for 6m² REPRESENTATION.</p>	<p data-bbox="1249 394 1449 562">Adequate ventilation to be arranged before work commences IAW General 3.2.</p> <p data-bbox="1249 595 1449 707">IAW Paint scheme -General 12 and Annex B refer.</p>

TASK NO.	TASK/DESCRIPTION	NOTES
H8.05	<p data-bbox="517 327 1114 353">H8 INTERNAL DECKS, DOORS AND LADDERS</p> <p data-bbox="397 387 855 421">Tank Deck Training Area Ladders</p>  <p data-bbox="397 920 1209 1021">Both tank deck gantry access ladders showing breakdown of paint coverings. REPRESENT both ladders. ALLOW for 5m² REPRESENTATION.</p>	<p data-bbox="1246 387 1447 506">IAW Paint scheme -General 12 and Annex B refer.</p>

TASK NO.	TASK/DESCRIPTION	NOTES
	H8 INTERNAL DECKS, DOORS AND LADDERS	
H8.06	<p data-bbox="408 421 823 454">Main Engine Room Deckplates</p> <div data-bbox="408 472 1236 837">  </div> <p data-bbox="408 853 1214 1021">Engine room deckplates are loose in many areas and require re-securing. Some deckplates are missing. All loose items currently blocking access throughout engine room walkways are to be removed and disposed of. Deckplates to be re-secured and missing deckplates manufactured and replaced with comparable checker-plate to current fit.</p> <p data-bbox="408 1039 1190 1068">ALLOW for 80 man hours. ALLOW for 15m² deckplate replacement.</p>	

TASK NO.	TASK/DESCRIPTION	NOTES
H8.07	<p data-bbox="512 360 1114 389">H8 INTERNAL DECKS, DOORS AND LADDERS</p> <p data-bbox="397 421 742 454">Machinery Control Room</p> <div data-bbox="397 468 1185 1055">  </div> <p data-bbox="397 1070 1214 1182">The Machinery Control Room (MCR) is currently not used for training purposes and contains a large amount of unused material. Contractor is to remove and dispose of all loose material to allow it to become a the training zone.</p>	<p data-bbox="1246 427 1425 551">To be done in conjunction with L1.02 – Training Zone Lighting</p>