

Works to Anglo-American Playing Fields 2019

Please find below the itemised quotation as requested;

- 1) Road from gates down to bridge.
To carefully remove material one side to widen road to 3metres total and install a timber edge.
Lay geotextile, type 1 and 10mm tarmac to suit.
Include three sections to repair.
Overlay the entire run with new Tar and Chip with buff gravel.
£

- 2) Area by gate
To dig out to new levels, base and tarmac and tar and chip (to be carried out with a larger section)
£

- 3) Road from bridge up to clubhouse
To address right hand side with new edging kerbs to retain soil 20 metres
To dig out and base/ tarmac worn areas which total 180m², including gate area with edgings as discussed.
To tar and chip entire run.
£

- 4) Grass area in front of hut 105m²
Full dig and makeup
Tar and chip carried out with other work but included in cost
£

- 5) Speed humps on access road in
5 No speed humps to be installed
3 existing to be added to, 2 new ones made from scratch.
£











