

Notes:

All trees to be protected during the works as per BS5837 'Trees in relation to Construction'.

No materials to be stored within the tree root zone (5m diameter around each tree).

Tree guards and grilles to remain on trees 1 & 2.

Tree 3 to be relocated see General Arrangement Drawing (172-03) and 'Tree Planting Details' (172-06).





