Job No : 70020998 | Drg No: 1704

Prepared by: JM | Sheet No: 1 of 1

Site ref: **Treluswell Retaining Wall** | Date prepared : 23.08.2016 | Revn : 0

Parapet Reinforcement Details | Date revised : | Status: D/P

Member	Bar mark	Type and size Type	ϕ	No. of mbrs	No. of bars in each	Total no.	Length of each bar † mm	Shape code	A* mm	B* mm	C* mm	D* mm	E/R* mm	Rev letter
Parapet	01	H	12	9	68	612	2175	21	975	175	975			
	02	H	10	9	46	414	2350	00	2350					
	03	H	12	9	17	153	1350	51	400	175	160	125		

This schedule complies with BS 8666:2005

* Specified in multiples of 5mm. † Specified in multiples of 25 mm.

Status: P Preliminary T Tender C Construction