

Price List					
Name	603426 M5 Blackbrook Interchange Crossovers				
Contractor	[Contractor to state name]				
Guidance notes & preamble for the Contractor					
The Contractor is paid in accordance with Clause 50 & 51. The rates and prices entered in the Price List shall be deemed to be the full inclusive value of the work covered by the items					
You are required to submit a Rate or Price for each Item associated with the Providing the Works					
Where an Item has specified Quantity, you should enter a value in the Rate column and the Price for each Item should be equal to the specified Quantity multiplied by your submitted Rate. Payment for these items will be made in accordance with the Contract i.e. total Quantity completed multiplied by the Rate.					
For Items where the unit is specified as 'lump sum' you should submit a Price only.					
All Rates and Prices must be quoted in pounds and whole new pence to two decimal places and exclude VAT. Any item priced as zero must be explained within your tender proposal.					
You should ensure the total is correct before submission. If necessary, the Employer may contact a tenderer whose Offer has required an arithmetical adjustment.					
Price List Part 2					
Item No.	Item Description	Unit	Quantity	Rate	Price
BX01	Mobilisation and site set-up	Item	1	£0.00	£0.00
BX02	Targeted Asbestos Survey and refurbishment survey of a Highways Drainage network including a desktop study and sampling on site survey area highlighted on drawings HE603426-KIER-VDS-M5_J25_MP_205.0-210.2_Z-DR-CB-00002 DRAINAGE	Item	1	£0.00	£0.00
BX03	Reporting as detailed in the Works Information, including photographs	Item	1	£0.00	£0.00
BX04	Trial Pits in "soft" central reserve 1.0m deep as shown on drawingHE603426-KIER-VPS-M5_J25_MP_205.0-210.2_Z-DR-CB-00001	no	11	£0.00	£0.00
BX05	Report on trial holes as per Specification in Works information	no	1	£0.00	£0.00
BX06	Sampling and soil contamination testing (POPs and Standard Waste Suite) including issuing of results as shown on drawing HE603426-KIER-VPS-M5_J25_MP_205.0-210.2_Z-DR-CB-00001	no	11	£0.00	£0.00
BX07	Dynamic Cone Penetration Survey (DCP) and reporting of resulting data as shown on drawing HE603426-KIER-VPS-M5_J25_MP_205.0-210.2_Z-DR-CB-00001	no	13	£0.00	£0.00
BX08	150mm diameter coring of bituminous pavements and photographing, logging of subsequent cores and reinstatement of pavement during night time.	no.	2	£0.00	£0.00
BX09	PAK marker test	no.	2	£0.00	£0.00
BX10	Provisional item PAH and Phenol analysis (Possible follow up PAH lab testing if any positive PAK test identified / requirement for PAH tests to be agreed on receipt of the report)	no.	0	£0.00	£0.00
total of the Prices					£0.00

One programme can be submitted to cover all surveys, however, you must ensure all locations and site activites are detailed separately within the prgramme  
Any programme which does not adequately detail all site activites and locations may lead to a failed assessment