

Quorn Parish Council - Christmas Lights Specification

Main Contract works:

Pre-Season

Carry out pre-season health check to power supplies. Inspect wiring and accessories and check operation of safety RCBO's, timeclocks etc.

Carry out pre-season inspection of clients' own decorations, check wiring, connections, plug, joint boxes etc, test operation and carry out PAT testing. On completion, provide report to client advising of any issues found with costs for rectification works.

Installation Scheme – Plan Area 1

Provide Engineers and Powered access equipment to install clients' own equipment and re-commission displays which remain in situ. All equipment to be tested and made ready for switch-on.

Displays to cover the following areas:

1.1 Station Road

- Icicles to Buildings – Quorn Cross to Park entrance
- Icicles to 'Bianca's Pizza'

1.2 Old School

- Icicles to building – fronting park

1.3 High Street

- Icicles to buildings – Quorn Cross to The Banks

1.4 The Banks

- Commission Natural trees
- Festoon Churchyard path from Church Lane to Station Road

1.5 Village Hall

- Supply Icicles
- Install 2 no. Lantern decorations
- Install 2 no. Sphere decorations

Christmas Trees – stand alone

1.7 Dress Tree at The Banks – multi colour

1.8 Dress Tree at Memorial Gardens – multi colour

**NB: No catenary wires across highway.
Remove any redundant lights from previous installations
All power supplies to be from Parish Council metered feeder pillars.**

Switch On

Provide 2 no. Engineers to attend switch on event. On completion, set all timeclocks for normal running times of 1600 to 0100 and secure all columns and enclosures.

Display Enhancements for 2019	
<p>Natural Trees – Station Road Car Park – Plan Area 2</p> <p>Remove existing damaged light sets and cart away. Supply and install new LED lighting sets connected to existing power supply. LED garlands draped (to match existing) bright white static/black cable (Total of 1200LED's) with associated transformers. Lights to be secured to the ends of branches.</p> <p>Cost per tree:</p> <p>Natural Trees – The Banks – Plan Area 3</p> <p>To remove existing light sets and cart away. Supply and install new LED lighting sets connect to existing power supplies. LED garlands draped to be multi-coloured static/black cable with associated transformers.</p> <ul style="list-style-type: none"> • Small Trees at back – 400 LEDs • Larger Trees at front – 1365 LEDs <p>Cost per tree: Cost per tree:</p>	
<p>Icicles – Village Hall Building – Plan Area 4</p> <p>Replace existing LED icicles. Remove existing and set aside for client. Supply and install new LED icicles and connect to existing power supplies.</p> <p>Product</p> <p>LED icicle light sets. Bright White/Static/White Cable 0.5mt drop x 3mt length</p> <p>Installation</p> <p>Labour and powered access equipment to remove and install new equipment.</p> <p>Lights will remain in situ at end of season.</p>	
<p>Removal Scheme</p> <p>All lights to be switched off and dismantled, labelled, packed and stored for 11 months pending the award of subsequent contract.</p>	