

**National Asset Delivery
Technical Surveys and Testing**

**M69 SB M1 to J1 Pavement & Lining
Stage 1 - Deflectograph**

Scope

TABLE OF CONTENTS

1 PURPOSE OF THE SERVICES4

2 EXISTING INFORMATION5

3 CONSTRAINTS ON HOW THE CONSULTANT PROVIDES THE SERVICES ...6

4 REQUIREMENTS FOR THE PROGRAMME8

5 SERVICES AND OTHER THINGS PROVIDED BY THE CLIENT9

6 SPECIFICATION FOR THE SERVICES10

LIST OF ANNEXES

Appendix 1 Supplementary Constraints

DO NOT USE INFORMATION ONLY COMPLETE AT THIS STAGE

1 PURPOSE OF THE SERVICES

1.1 Project objectives

1.1.1 The principle objective of this project is to undertake Deflectograph surveys at the locations stated in HE601892-KIER-HPV-M69_ML_M1_JN1_B-SH-CH-01 Schedules and Plans and provide subsequent reports and testing in accordance with the requirements detailed in the specification.

1.1.2 The specification that applies to the services is included in Section 6.

1.2 Scope of services

1.2.1 The services to be provided under this contract are:

- (1) The total scheme extents require a Category 1A Deflectograph survey for the lanes identified in the schedule ref HE601892-KIER-HPV- ML_M1_JN1_B-SH-CH-01 Schedules and Plans.
- (2) Contractor to propose the temporary traffic management they require. Once agreed Employer will provide the temporary traffic management.

1.3 Deliverables

1.3.1 The *Consultant* is required to produce the following deliverables:

Deflectograph

- (1) The survey shall be carried out in accordance with DMRB CS 229 and the resultant data processed and uploaded into HAPMS.

2 EXISTING INFORMATION

2.1.1 The Drawings listed below apply to this contract.

2.1.2 Refer to the site information for details of existing site conditions including ground conditions, limitation on access, position of existing structures etc.

Drawing Number	Title	Revision / Date
HE601892-KIER-GEN-M69_ML_M1_JN1_B-DE-Z-0000-01	Location Plan	P01
HE601892-KIER-HPV-M69_ML_M1_JN1_B -SH-CH-01 Schedules and Plans	Coring/DCP/Deflectograph/UMS Schedule and Plan	
HE601892-KIER-VGN-M69_ML_M1_JN1_B -DE-CH-0000-01 to 13	Coring/DCP/Deflectograph & UMS Plans	
HE601892-KIER-VUT-M69_ML_M1_JN1_B -DE-Z-2700 01 to 16	Statutory Undertakers Drawings	P01

3 CONSTRAINTS ON HOW THE CONSULTANT PROVIDES THE SERVICES

3.1 General

3.1.1 The *Consultant* Provides the Services in such manner as to minimise the risk of damage or disturbance to or destruction of third party property.

3.1.2 The *Consultant* complies with the constraints and meets with the requirements outlined in Appendix 1.

3.1.3 The *Consultant* submits information detailing how the *Consultant* will provide the Services to the *Client* prior to the *services* commencing. This information will include any lifting plans, risk assessments, method statements, the *Consultant's* staff training information and any other relevant Health and Safety requirements.

3.2 Working hours & site specific constraints

3.2.1 The *Contractor's* working hours for site works shall be 20:00 to 05:00.

3.2.2 Weekend working shall be permissible.

3.2.3 Provisional Road space availability begins on the 13/07/20 at 20:00 and ends on the 17/07/2020 at 05:00.

3.2.4 Refer to environmental assessment.

3.3 Health, Safety and Environment & Risk Management

Health and Safety requirements

3.3.1 In Providing the Services the *Consultant* meets the requirements of Annex 2 of the supplementary constraints relation to health and safety duties.

3.3.2 When implemented, the *Consultant* shall comply with the requirements of Highways England's safety passport scheme and ensure that all of his employees, and any of his subcontractor's, are registered in accordance with the implementation of the scheme.

3.3.3 For details of the CDM duty holders, refer to the pre-construction information which can be found here HE601892-KIER-GHS- M69_ML_M1_JN1_B -HS-ZS-01_Pre-Construction Information.

3.3.4 Before commencing the construction phase of the *services*, the *Consultant* confirms to the *Client* that adequate welfare facilities are in place. Where the facilities detailed in section 5 are not deemed adequate, the *Consultant* provides all necessary facilities to Provide the Services and to comply with the minimum requirements set out in HSE guidance document L153.

Environmental requirements

- 3.3.5 In Providing the Services the *Consultant* meets the requirements of Annex 2 of the supplementary constraints in relation to environmental duties.

Risk Management

- 3.3.6 The *Consultant* identifies, manages and mitigates risks in accordance with the principles of ISO31000.
- 3.3.7 The *Consultant* submits a risk register, which captures all risks associated with the delivery of the *services* including those identified by the *Client*, with his tender and maintains it for the contract period.

DO NOT COMPLETE AT THIS STAGE

4 REQUIREMENTS FOR THE PROGRAMME

- 4.1.1 The *Consultant* submits programme to the *Client* with his tender.
- 4.1.2 The *Consultant* Provides the Services taking into account the following programme constraints:
- (i) the *starting date* and *completion date* and any post site works, reporting and review period
 - (ii) The services and other things provided by *Client* (see Section 5)
- 4.1.3 The programme should be in the form of an activity and time related bar chart, produced as a result of a critical path analysis.
- 4.1.4 The programme should preferably be provided in either a PDF or MS Excel format and cover the full contract period including post site activities. Activities should be clearly defined and named and the programme should detail the following:
- (i) dates and times associated with the project, including the *starting date*, *completion date* & *Consultant's* planned completion, and any other dates or times that will specifically impact the delivery of the project
 - (ii) activities associated with delivering the project
 - (iii) key dates for co-ordination with Others
- 4.1.5 The *Consultant* should provide details of the proposed resources (plant, labour, subcontractors etc.) expected to deliver each activity. This information can either be shown on the programme itself or provided in an associated resource statement included in the Proposal for Providing the Services.
- 4.1.6 The *Consultant* updates the programme week. The *Consultant* submits an updated programme to the *Client* upon request.

5 SERVICES AND OTHER THINGS PROVIDED BY THE *CLIENT*

5.1.1 The following temporary traffic management will be provided by the *Employer* to allow the *Contractor* to Provide the Works:

- (i) Assumed traffic management for this is as follows;
 - Varying lane/hard shoulder closures for main carriageway as required.

- (ii) *Contractor* to liaise with *Employer* regarding the Temporary traffic management they require to carry out the works.

5.1.2 The other things that will be provided by the *Employer* are as follows:

- (i) Welfare facilities will be provided by the Principal Contractor
- (ii) Desktop search for utility information (PAS128 Type D) survey. This information will be provided to the contractor at the pricing stage. The contractor is not required to send out for this information again.

6 SPECIFICATION FOR THE SERVICES

6.1.1 The *Consultant* shall Provide the Services in accordance with National AD Technical Surveys & Testing contract documentation as well as the additional requirements:

6.1.2 The Deflectograph survey shall be carried out in accordance with DMRB CS 229.

FOR INFORMATION ONLY
DO NOT COMPLETE AT THIS STAGE