

Safe roads, reliable journeys, informed travellers

Area 3 ASC

LNMS Scheme L3A

Scheme Brief

Area 3 ASC

LNMS Scheme L3A
Scheme Brief

AMENDMENT RECORD

Amend . No.	Issue Date	Amendments	Initials	Date
0	August 2012	First Issue	SOS	21/8/12

1 Scheme Type

This scheme is a value band A (£0 to £30k), LNMS Scheme.

2 Scheme Description

This is a scheme to improve signing along strategic emergency diversion routes. The works will incorporate both the replacement of a number of existing signs and the provision of new signs to be placed on either new or existing posts.

The works will include but is not limited to:

- Provision of temporary accommodation or all necessary facilities to meeting health and safety requirements;
- Removal of no more than 6 existing signs, including removal of existing posts and concrete foundations where required;
- Provision and installation of not more than 7 new traffic signs over various sizes including provision of new posts, foundations and all associated works;
- Provision and installation of not more than 23 new traffic signs of various sizes to be located on existing posts;
- Vegetation clearance to improve visibility of a total of 32 new and existing signs covering a total area of no more than 100m².

3 Road category on which the work is to be carried out

The works will take place on several different single carriageway \leq 9m wide (rural – greater than 40 mph) roads.

4 Traffic Management

The provision of traffic management is outside the scope of this scheme.

5 Period within which the work is to be carried out

The works are to be carried out within Time Band 6.

6 Site Restrictions and Constraints

The following restrictions and constraints exist at the works location:

 Works will take place at numerous locations and on roads which are not maintained by the Highways Agency.

7 Indicative Programme and Season within which the work is to be carried out

Area 3 ASC

LNMS Scheme L3A
Scheme Brief

The works are to be completed within 5 days.

The majority of the works are to be constructed during British Summer Time.