

Engineering and Construction Short Contract

Contract Data Forms

June 2017 (with amendments January 2023)

Template version history

V1 (as per bidder pack)	Go live template

NEC4 Engineering and Construction Short Contract

The Environment Agency
Horizon House
Deanery Road
Bristol
BS1 5AH
Land & Water Services Ltd
Burpham Court Farm Breach Repair
Contract Forms - Contract Data - The Contractor's Offer and Client's Acceptance - Price List - Scope - Site Information

The <i>Client's</i> Cor	ntract Data		
	The Client is		
Name	Environment Agency		
Address for communications	Red Kite House, Howbery Busine OX108BD	ess Park, Wallingford, Oxfordshire	
Address for electronic communications	And		
The works are	Construction involving the repair of breached section of bank along River Wey and in-channel habitat works in fish bypass channel.		
The site is	Burpham Court Farm near Guildford, GU47NA (centred at NGR TQ0061052856)		
The starting date is	13/02/2025		
The completion date is	01/11/2025		
The delay damages are	£217.59 Per day		
	•		
The <i>period</i> for reply is	2	weeks	
	•	1	
The defects date is	104	weeks after Completion	
	ı	1	
The defects correction period is	4	weeks	
	<u> </u>	<u>I</u>	
The assessment day is	the last working day	of each month	
	l	<u> </u>	

The retention is	nil	%
		·
The United Kingdom Housing Grants, Construction and Regeneration Act (1996) does apply		
The <i>Adjudicator</i> is :		
In the event that a first dispute is referred to adjudication, the referring Party at the same time applies to the Institution of Civil Engineers to appoint an <i>Adjudicator</i> . The application to the Institution includes a copy of this definition of the <i>Adjudicator</i> . The referring Party pays the administrative charge made by the Institution. The		

person appointed is also Adjudicator for later disputes.

The Client's Contract Data The interest rate on late payment is % per complete week of delay. Insert a rate only if a rate less than 0.5% per week of delay has been agreed. For any one event, the liability of the The Contract Price Contractor to the Client for loss of or damage to the Client's property is limited The Client provides this insurance None Insurance Table Event Cover Cover provided until Loss of or damage to the works Replacement Cost The Client's certificate of Completion has been issued Loss of or damage to Equipment, Plant and Materials The defects Certificate Replacement Cost has been issued Minimum £5,000,000 in The Contractor's liability for loss of or damage to property (except the works, Plant and Materials and Equipment) respect of every claim

employ	and for bodily injury to or death of a person (not an employee of the <i>Contractor</i>) arising from or in connection with the <i>Contractor's</i> Providing the Works					
Contra	y for death of or bodily injury to empector arising out of and in the comment in connection with this contract	ourse of their	The amount required by the applicable law			
Failure of the Contractor to use the skill and care normally used by professionals providing works similar to the works			Minimum Contract Price in respect of every claim without limit to the number of claims	6 years following Completion of the whole of the <i>works</i> or earlier termination		
The Ad	djudicator nominating body is	The Institution	of Civil Engineers			
T . (:		Lee e ca				
The trii	bunal is	litigation in the	courts			
<u>-</u> ,				0047 (; 1 1;		
	enditions of contract are the NEC4 En emendments) and the following addition		Construction Short Contract	June 2017 (including		
_	enter details here if additional cond	itions are requ	iired.			
Z1.0	Sub-contracting Sub-contracting					
Z1.1	1.1 The Contractor submits the name of each proposed subcontractor to the Client for acceptance. A reason for not accepting the subcontractor is that their appointment will not allow the Contractor to Provide the Works. The Contractor does not appoint a proposed subcontractor until the Client has accepted them.					
Z1.2	Payment to subcontractors and suppliers will be no more than 30 days from receipt of correct invoice.					
Z2.0	Environment Agency as a regulatory authority					
Z2.1	The Environment Agency's position as a regulatory authority and as <i>Client</i> under the contract is separate and distinct. Actions taken in one capacity are deemed not to be taken in the other.					
Z2.2	Where statutory consents must be obtained from the Environment Agency in its capacity as a regulatory authority, the <i>Contractor</i> is responsible for obtaining these and paying fees (unless stated otherwise in the Scope). The <i>Client's</i> acceptance of a tender and the <i>Client's</i> instruction or variation of the <i>works</i> does not constitute statutory approval or consent.					
Z2.3	2.3 An action by the Environment Agency as regulatory authority is not in its capacity as <i>Client</i> and is not a compensation event.					
Z3.0	Confidentiality & Publicity					
Z3.1	The Contractor may publicise the works only with the Client's written agreement.			ent.		
Z4.0	Correctness of Site Information					
Z4.1	Site Information about the ground, subsoil, ducts, cables, pipes and structures is provided in good faith by the <i>Client</i> but is not warranted correct. The <i>Contractor</i> checks the correctness of any such Site Information they rely on for the purpose of Providing the Works.					
Z5.0	The Contracts (Rights of Third Parti	,				
Z5.1	For the purposes of the Contracts (Rights of Third Parties) Act 1999, nothing in this contract confers or purports to confer on a third party any benefit or any right to enforce a term of this contract.					
Z6.0	Design					
Z6.1	Where design is undertaken, it is the obligation of the <i>Contractor</i> to ensure the use of skill and care normally used by professionals providing similar design services.					

Z6.2	The Contractor designs the parts of the works which the Scope states they are to design.
Z6.3	The Contractor submits the particulars of their design as the Scope requires to the Client for acceptance. A reason for not accepting the Contractor's design is that it does not comply with either the Scope or the applicable law.
	The Contractor does not proceed with the relevant work until the Client has accepted this design.
Z6.4	The Contractor may submit their design for acceptance in parts if the design of each part can be assessed fully.
Z7.0	Change to Compensation Events
Z7.1	Delete the text of Clause 60.1(11) and replace by:
	The works are affected by any one of the following events
	War, civil war, rebellion revolution, insurrection, military or usurped power
	Strikes, riots and civil commotion not confined to the employees of the <i>Contractor</i> and sub-contractors
	Ionising radiation or radioactive contamination from nuclear fuel or nuclear waste resulting from the combustion of nuclear fuel
	Radioactive, toxic, explosive or other hazardous properties of an explosive nuclear device
	Natural disaster
	Fire and explosion
	Impact by aircraft or other device or thing dropped from them
Z8.0	Framework Agreement
Z8.1	The Contractor shall ensure at all times during this contract it complies with all the obligations and conditions of the Framework Agreement made with the Client.
Z9.0	Termination
Z9.1	Delete the text of Clause 92.3 and replace with:
	If the <i>Contractor</i> terminates for Reason 1 or 6, the amount due on termination also includes 5% of any excess of a forecast of the amount due at Completion had there been no termination over the amount due on termination assessed as for normal payments.
Z10.0	Data Protection
Z10.1	The requirements of the Data Protection Schedule shall be incorporated into this contract
Z11.0	Liabilities and Insurance
Z11.1	Civil data protection claims and regulatory fines for breaches of Data Protection Legislation are excluded from any limit of liability stated.
Z110	Inflation
	At the Contract Date the total of the Prices does not include a sum to cover inflation.
	The total of the Prices [at the Contract Date] shall be adjusted by a fixed number of Price Adjustments.
	The number of Price Adjustments shall be equal to:
	The number of months between the Completion Date included at the <i>starting date</i> and the Contract Date.
	The proportion of Price Adjustment shall be equal to:
	The total of the Prices at the Contract Date / The number of Price Adjustments

Each time the amount due is assessed, the Price Adjustment shall be:

The proportion of Price Adjustment x [80% x Construction Output Price Indices (OPIs) New work output prices: Infrastructure Index 1 – month rate]

The Construction Output Price Indices (OPIs) New work output prices: Infrastructure Index 1 – month rate shall be the value determined by the Office of National Statistics for the applicable month of the amount due assessment

Provided always that the fixed number of Price Adjustments has NOT been exceeded.

The Price Adjustment adjusts the total of the Prices.

If a compensation event under this contract omits original Scope covered by the total of the Prices at the Contract Date the Price Adjustments made under this clause shall be corrected accordingly.

The Contractor's Contract Data			
	The Contractor is		
Name	Land & Water Services Ltd		
Address for communications	Land & Water Services Ltd		
	Albury Mill,		
	Chilworth		
	Surrey		
	GU4 8RU		
Address for electronic communications			
The fee percentage is	As framework	%	
The people rates are	As framework		
category of person	unit	rate	
		<u></u>	
The published list of Equipment is		As framework	

The percentage for adjustment for Equipment is	As framework

The Contractor's Offer and Client's Acceptance

The Contractor offers to Provide the Works in accordance with these conditions of contract for an amount to be determined in accordance with these conditions of contract. The offered total of the Prices is £193,735.00 Enter the total of the Prices from the Price List. Signed on behalf of the Contractor Name Position Commercial Director Signature 31.01.25 Date The Client accepts the Contractor's Offer to Provide the Works Signed on behalf of the Client Name Position Fisheries, Biodiversity & Geomorphology Project Manager

Signature	
Date	06/02/2025

Price List

Entries in the first four columns in this Price List are made either by the Client or the tenderer.

If the *Contractor* is to be paid an amount for the item which is not adjusted if the quantity of work in the item changes, the tenderer enters the amount in the Price Column only: the Unit, Quantity and rate columns being left blank.

If the *Contractor* is to be paid an amount for the item of work which is the rate for the work multiplied by the quantity completed, the tenderer enters the rate which is then multiplied by the expected quantity to produce the Price, which is also entered.

Item Number	Description	Unit	Quantity	Rate	Price
	Precommencement Works				
1	Preconstruction Project Management and production of Construction Phase Plan (CPP) and other associated documents required by SHEW CoP (version 6)	Sum	1		
2	Design – Temporary works	Sum	1		
3	Design – Permanent works	Sum	1		
4	Preparation and submission of information to Thames Water	Sum	1		
5	CCTV survey of pipe crossing prior to mobilisation onto site	Sum	1		
6	Meetings with other Contractors	Sum	1		
	Thames Water TWOSA (not required)				Not priced

	Advance Works			
7	Vegetation Clearance of existing mature grassland (not previously strimmed) in southern fish pass field before bird season commences (if required)	Sum	1	
8	Vegetation Clearance of all working areas down to ground immediately before construction to avoid harm to reptiles/amphibians (if not being provided by Guildford Borough Council's Contractor)	Sum	1	
9	Tree protection (if not being provided by Guildford Borough Council's Contractor)	Sum	1	
10	Materials - Temporary Works	Sum	1	
11	Materials - Permanent Works – Breach repair	Sum	1	
12	Materials - Permanent Works – Habitat redevelopment, including 8 tonne of gabion stone (100-200mm), 20 tonne of 20-40mm angular flinty/golden gravel	Sum	1	
	Site Works			
13	Mobilisation	Sum	1	
14	Project management, Supervision and welfare	Sum	1	
15	Install and maintain temporary works	Sum	1	
16	Construct breach repair	Sum	1	
17	Construct Habitat redevelopment - Install riprap and gravel to EA requirements	Sum	1	
18	Waste recycling	Sum	1	
19	Demobilisation	Sum	1	
20	Reinstatement of land access routes	Sum	1	
	Post completion			
21	CCTV survey of Thames Water pipeline	Sum	1	
22	Post construction documents – "As Built" drawings, Health and Safety File (including information on materials used and maintenance): To be provided within a month of project Completion	Sum	1	
23	Completion of the Environment Agency's Carbon Calculator and Final Carbon Report for the 'as built' project to be provided within a month of project Completion.	Sum	1	
			-	
	The	total of	the Prices	£193,735.00

The method and rules used to compile the Price List are

Civil Engineering Standard Method of Measurement 4th edition (CESMM4) as per the Framework Price Workbook.

Scope

The Scope should be a complete and precise statement of the *Client's* requirements. If it is incomplete or imprecise there is a risk that the *Contractor* will interpret it differently from the *Client's* intention.

1. Description of the works

Give a detailed description of what the *Contractor* is required to do and of any work the *Contractor* is to design.

Background information

In 2023 a naturalised fish bypass channel was built around Bowers Old Bucks weir at Burpham Court Farm (BCF), near Guildford. This will benefit migratory fish such as trout and eels and all other fish species which rely on the ability to freely move between different habitat types to complete their lifecycles. A planning application for the scheme was approved by Guildford Borough Council (18/11/2022).

The *site*, which is centred at approximately TQ0080352647, is owned by Guildford Borough Council (GBC), and runs alongside the Wey Navigation (National Trust). The Environment Agency instructed Land and Water Services to build the 275m long channel which incorporates three backwater features, with construction completing in Autumn 2023. Immediately post construction work, following repeated and significant flooding, there was a bank failure immediately adjacent to the fish pass offtake structure. This resulted in a bank breach and mobilisation of habitat features immediately downstream of the fish pass structure. To secure the benefits of the project and overall programme, the breach will need to be designed and repaired to prevent future breaches, and habitat features will need to be redeveloped to secure scheme objectives. Design services will involve the design of temporary *works* to manage flows and for access.

Project deliverables

The *Contractor* is to Design and Build a solution that shall consider cost, buildability, carbon, landowner requirements and aesthetics. The objectives of the *works* are:

- to be compatible with the original design of the fish bypass channel (see Drawings list provided)
- to prevent any scour/erosion around the fish pass structure
- · have no impact on water levels in the Wey navigation
- have no encroachment into the Wey navigation
- ensure the footbridge crossing over the fish pass exit structure remains accessible from either bank
- shall be as natural and sustainable as possible, encouraging the development of habitats
- · to be acceptable to the Environment Agency, National Trust and Guildford Borough Council.

The Contractor shall:

- Design and install temporary works as required. Dam sections must adhere to all current temporary works regulations. Works cannot commence on site before the Client accepts the design. The Contractor must ensure contingency planning is in place to remove any temporary works, plant, compound, welfare facilities etc. in a flood.
- Liaise with Environment Agency Fisheries Specialists with regards to dewatering activities, including closing of the fish pass for works. This may necessitate a fish rescue performed by Environment Agency staff, which will need to be allowed for in the programme. Closure of the fish bypass channel and fish rescue is planned for week commencing 24th February 2025, to be performed by the Environment Agency, with a duration of 2 working days.
- Assist the Environment Agency with agreeing access with the landowners and the location of any compound and welfare facility. The *Client* will lead and be responsible for access arrangements.
- Access arrangements will need to have consideration of the project's approved Red Line Boundary.
- Liaise with Thames Water regarding proposed equipment and method of works associated with crossing main sewer line.
- Provision of welfare facilities and a compound area as required.
- Provision of traffic management as required.
- A detailed photographic record of access routes and all working areas must be carried out by the Contractor prior to works commencing on site and provided to the Client. All access routes and working areas must be reinstated on Completion of the works.
- Provide details, to be accepted by the Client, of any crossings planned over the fish bypass channel to minimise ecological and morphological harm.
- Liaise with the National Trust regarding water level management and impacts to river users during the works
- Design and installation of bank repair solution, and erosion protection on south-west bank
 (upstream and downstream of fish pass structure, on both the inside and north-east banks –
 see indicative diagram below). Design option to be informed by the outcome of the
 Optioneering Contract (Burpham Court Farm breach repair feasibility Land & Water –
 1070174992) and the advice given by the Environment Agency to provide a sustainable,
 naturalised design solution. Construction should be timed so that the bank repair solution is
 completed to maximise the establishment of vegetation before potential high flows. The


- design needs to be reviewed and accepted by the Environment Agency, National Trust and Guildford Borough Council. Preferred *Client* option from Optioneering stage: sheet piling temporary *works*, fish pass bridge realigned to central position to allow for 1.5 slope on the breach repair, composite turf covering the breach, riprap on other areas of potential erosion.
- Identify, plan and procure any surveys and/or investigations required by the temporary and permanent work designs e.g. Ground investigations, GPR surveys
- Liaise with Guildford Borough Council and their Suitable Alternative Natural Greenspace
 contractor to effectively programme activities and site operations. Guildford Borough Council
 will have contractors on-site during 2025. The Contractor will act as Principal Contractor, and
 agree access and a segregated work and compound areas.
- Plan and execute necessary vegetation clearance for access routes, and reinstate access routes following construction. This should be planned to avoid breeding bird season, and to minimise the risk to reptiles/amphibians by plant movements.
- Build of earthworks to redevelop habitat features immediately downstream of fish pass structure under the supervision of Environment Agency Fisheries and Geomorphology Specialists. This will involve introducing additional gravel to the channel and redistributing existing gravel. The *Contractor* should use gravel already on *site* where possible.
- Once the habitat features have been redeveloped, ensure the fish pass operates effectively
 with full design flow whilst the *Contractor* is still mobilised and can adjust features under the
 supervision of Environment Agency Fisheries and Geomorphology Specialists. This should
 be clearly identified and allowed for in the programme. The *Contractor* should allow for 1 full
 working day to allow for the fish pass to be reopened, the channel to be assessed
 Environment Agency Fisheries and Geomorphology Specialists, and subsequent gravel
 movements undertaken using on-site machinery.
- Management and disposal of waste in accordance with the Environment Agency's SHEW
 Code of Practice
- Before Completion, an input to a suitably developed Health and Safety File must be issued
 to the Principal Designer along with 'as built' drawings (provided in CAD and pdf format)
 showing any changes from the original design.
- The Successful Contractor should complete an Environment Agency Carbon Calculator. This
 is the Environment Agency's tool for assessing whole life carbon. To support the Client in
 cutting carbon emissions, the Contractor must complete monthly carbon reporting, an 'as
 built' Carbon Calculator and Final Carbon Report within one month of Completion of the
 works.
- Refer to and update existing site documentation where available from original construction period to reflect new site conditions, working arrangements and designs etc.

The Contractor shall also:

- Fulfil the duties of Principal Contractor and Designer in CDM 2015 regulations. Duties will include, but are not limited to, producing the temporary works schedule, completing the RAG list and liaising with the Client, the EA's appointed Principal Designer, and Guildford Borough Council's Contractor for the Suitable Alternative Natural Greenspace construction.
- Have Design duties covering the breach repair solution and erosion protection on the southwest bank. Design duties are not required for the habitat redevelopment works.

- Liaise with the *Client* and the Principal Designer on matters relating to the delivery of the project, compliance with the CDM regulations, flood risk management, regulatory compliance, ecological stewardship and the programme. The *Contractor* must do the *works* considering the information provided in the PCI.
- ➤ Ensure that the breach repair and habitat redevelopment are created according to the design. The works must be inspected and accepted by the Environment Agency's Fisheries team
- Agree the specification of aggregate materials for the channel substrate with the Environment Agency's Fisheries team before ordering. Any gravel used to line the channel bed must be angular 20-40mm flinty/golden gravel. Any deviation from this needs to be accepted by the *Client*.
- Ensure that the land is reinstated upon Completion of the works to the satisfaction of GBC and the Environment Agency's Fisheries, Biodiversity & Geomorphology team.
- Comply with the Safety, Health, Environment and Wellbeing (SHEW) CoP
- Production of the Construction Phase Plan (CPP) and all other associated documents. A suitably developed CPP must be issued for acceptance no less than 10 days prior to planned mobilisation. Please refer to the previously approved CPP and the Pre-Construction Information (PCI) for further clarification of requirements for the CPP.
- Comply with the planning application and associated conditions (22/P/00881 Guildford Borough Council), with specific reference to discharge of conditions 3 & 4 (23/D/00054 Guildford Borough Council).
- Comply with previously approved EAP and update where instructed by Environment Agency Fisheries, Biodiversity and Geomorphology team.
- All communications are to be made electronically and will be agreed in detail at project start up. It is anticipated that monthly progress meetings, design review meetings and weekly site meetings during construction, will be held, and an allowance should be made for this, as well as ad hoc meetings as required to deliver the project.

Diagram illustrating works:



2. Drawings

List the drawings that apply to the contract.

Drawing Number	Revision	Title
5192284-ATK-PC- ZZ-DR-C-0004	1.6	GENERAL ARRANGEMENT OF PIPE CROSSING SLAB
5192284	2	GENERAL ARRANGEMENT PLAN
5192284-ATK-XX- ZZ-DR-C-0150-C4	C4	Fish pass channel plan and long section
5192284-ATK-XX- ZZ-DR-C-0151-C5	C5	Fish pass channel fish pass exit plan and cross sections
5192284-ATK-XX- ZZ-DR-C-0152 A- C4	C4	Fish pass channel fish pass entrance plan and cross sections
5192284-ATK-XX- ZZ-DR-C-0153-C2	C2	Backwater 1 plan, long section and cross sections
5192284-ATK-XX- ZZ-DR-C-0154-C2	C2	Backwater 2 plan, long section and cross sections
5192284-ATK-XX- ZZ-DR-C-0155-C2	C2	Backwater 3 plan, long section and cross sections
5192284-ATK-XX- ZZ-DR-S-0005	C02	General arrangement for fish pass exit structure

5192284-ATK-XX-	C03	Reinforcement details of fish pass exit structure sheet 01 of 03
ZZ-DR-S-0006		
5192284-ATK-XX-	C02	Fish pass exit structure walkway arrangement
ZZ-DR-S-0007		
5192284-ATK-XX-	C03	Reinforcement details of fish pass exit structure sheet 02 of 03
ZZ-DR-S-0008		·
5192284-ATK-XX-	C03	Reinforcement details of fish pass exit structure sheet 03 of 03
ZZ-DR-S-0009		·
A120101-TGEE-	C01	Burpham Court Site Hazard Plan
BC-19-DR-C-0001-		·
C01		
A120101-TGEE-	C01	Burpham Court Bund Layout
BC-19-DR-C-0002-		
C01		
		•

3. Specifications

List the specifications which apply to the contract.

Title	Date or Revision	Tick if publicly available
Environment Agency SHEW Code of Practice September 2023 (version 6)	Version 6	
2024 Asset Operation, Maintenance and Response Framework	2024	
Construction (Design and Management) Regulations 2015 (CDM 2015)	2015	

4. Constraints on how the Contractor Provides the Works

State any constraints on the sequence and timing of work and on the methods and conduct of work including the requirements for any work by the *Client*.

The *Contractor* shall not commence any *works* on the *site* until the *Client*, or their representative, has accepted the method statements and risk assessments related to this contract and provided authorisation in writing.

Burpham Court Farm is owned by Guildford Borough Council who are supportive of the work, but the Contractor will need to agree working methodologies and access agreements in advance of the works. The Client will be responsible for ensuring any land agreements are in place before the works commence. Guildford Borough Council will have contractors on-site during 2025 for the construction of the Suitable Alternative Natural Greenspace. It is anticipated that the *Contractor* will agree access and a segregated work and compound areas.

Burpham Court Farm is not currently accessible to the public (other than the occasional trespasser) but may be opened to the public in the future.

All temporary works and access arrangements around them will be sole responsibility of the Contractor.

There is a bridge over the River Wey which connects the north and south parts of the *site*. A structural assessment determining the loading capacity of the bridge was carried out by an ESE Contractor and will be available to the *Contractor*.

Construction of the bypass channel is close to Bowers Old Bucks Weir. *Contractor* will need to be considerate of Bowers Old Bucks Weir in their construction planning / methodology and adopt a method of working to protect the structure during the *works*.

Construction should be timed so that the bank repair solution is completed maximise the establishment of vegetation before high flows.

Thames Water are constructing a new sewer pipe within this project's red line boundary. Thames Water plan to have finished working within this project's red line boundary by planned start date. The Environment Agency will maintain contact with Thames Water. The *Contractor* should be informed if this situation changes.

The works are located within the floodplain. The Contractor will need to ensure that contingency planning is in place to remove any temporary works, plant, compound, welfare facilities etc. in the event of a flood.

The measures outlined in the Ecological Survey Report must be incorporated into the *Contractors* CPP/EAP and be complied with. This includes but is not limited to the following:

- 10m buffer zones along the River Wey and adjacent to wetland features. Buffers should be fenced
 with bunting or similar. Where a 10m buffer cannot be maintained along the River Wey or adjacent to
 wetland features (for example, alongside the pond near the site entrance and where the wetland
 feature and River Wey are very close to each other in the middle of the site), measures to prevent runoff should be considered.
- The Contractor will protect all of the retained trees and their Root Protection Areas (RPAs) within 10m of the proposed works with bunting or similar as outlined in the Arboricultural Impact Assessment and Tree Constraints Plan.
- Any tree or shrub clearance will be done outside of the bird breeding season (typically from March to August inclusive) where possible. This also applies to the existing mature grassland sward in the southern fish pass field where it has not previously been strimmed. If clearance is required within the main breeding bird season, vegetation must be checked for active nests by the EA's FBG team no more than 48 hours before removal. If an active nest is found, an appropriately sized exclusion zone will be set up around the nest until the young birds have fledged.
- To minimise the risk to amphibians/reptiles, the scrub/grass within the working area should be cut to 150mm and left for a minimum of 24 hours to allow amphibians/reptiles to move into surrounding habitat, followed by cutting the vegetation to ground level and leaving for a further 24 hour minimum period. Prior to strimming, the EA's FBG team will carry out a destructive finger-tip search of any potential refugia or hibernacula to allow any resting amphibians to move out of the area.
- If using percussive piling techniques: To minimise any impact, piling activities must avoid the coarse fish spawning season (15th March to 15th June inclusive). When piling, the rate of the driving hammer must be increased slowly over a 5-minute period to enable fish to swim away from the area before the full power of the pile hammer is felt. Piling must avoid early morning and late afternoon.
- If using vibro or silent piling techniques: Once the bypass channel is dewatered the risk to spawning fish is minimised. Piling can be undertaken within the fish spawning season.
- The location of Himalayan Balsam (and any other non-native invasive species) will be mapped and
 demarcated by the Environment Agency's FBG team before works commences to ensure these areas
 are avoided. Where excavation and/or vegetation clearance is required in these areas, the Contractor
 must separate and dispose of any arisings via a waste carrier that is licensed to take non-native
 invasive species. This will be given to the Contractor as an instruction.
- All works will follow up-to-date EA guidance regarding control measures when working in the vicinity
 of invasive species How to stop invasive non-native plants from spreading GOV.UK

The EA's FBG team will carry out an ecological walkover in advance of any vegetation clearance and the works themselves to check that no additional ecological constraints have arisen since the last survey was carried out. Any additional ecological constraints/mitigation required will be advised to the *Contractor* as an instruction and incorporated into the EAP.

The *Contractor* will plan *works* with consideration to the known archaeological features on *site*, as outlined in the "Burpham Court earthwork survey" produced by Oxford Archaeology.

The *Contractor* shall notify the *Client* of any issues that may affect residents or the public (e.g. piling) and the dates and times of expected disturbances.

At the pre-start up meeting the *Client* will advise which activities in the *Contractors* programme will be the subject of tests or inspections.

There is a Thames Water sewer that runs across the *site*. Thames Water have indicated that a Thames Water Operational Safety Authorisation (TWOSA) will not be required unless the *works* are intrusive (i.e. working inside a TW manhole or sewer). They will need to review proposed equipment and method of works to assure themselves that there is no increased risk of damage to their existing assets within the working zone. The *Contractor* is responsible for liaising with Thames Water on their requirements and obtaining their authorisation.

Doc No 249_18_SD15

Working times

The *Contractor* will be permitted to work between 7.30am and 6.00pm on weekdays (Monday to Friday), with piling restricted to the hours 9am – 5pm.

5. Requirements for the programme

State whether a programme is required and, if it is, state what form it is to be in, what information is to be shown on it, when it is to be submitted and when it is to be updated.

State what the use of the works is intended to be at their Completion as defined in clause 11.2(1).

The *Contractor* submits programme with the *Contractor*'s Offer for acceptance. The *Contractor* shows on each programme which they submit for acceptance (in form of Gantt chart showing the critical path, proposed order and timing to undertake the *works* and proposed plant and labour resources) the following:

- (a) Period required for mobilisation/ planning & post contract award
- (b) Contract starting date
- (c) Construction starting date
- (d) Each of the activities listed within the Price List, including activities which are dependent upon river level
- (e) Any key third party interfaces: lead in periods for materials and sub-contractors; time required to obtain consents/permits; stated constraints; *Contractor's* risks.
- (f) Completion date
- (g) Information to be provided, who it is to be provided by, and the date by which it is to be provided including anything required from the *Client*
- (h) Order and timing of tests, inspections and commissioning activities whether done by the *Contractor* or *Client* or others, including FBG inspection following the channel redevelopment *works*
- i) Design period
- i) Design review period
- k) Any surveys required to inform design

Following contract award, a programme is to be submitted every 4 weeks for acceptance by the Client

6. Services and other things provided by the Client

Describe what the *Client* will provide, such as services (including water and electricity) and "free issue" Plant and Materials and equipment.

Item	Date by which it will be provided
None	

Site Information

Further site information is included within the PCI: "PCI fish pass PCI"

There are two Thames Water manholes in land adjacent to the proposed fish bypass channel that are known to frequently surcharge raw sewage. Please report any pollution incidents to the EA Hotline - 0800 80 70 60.

Access:

- BCF Accommodation Bridge Details (Oct 1992)

Burpham Court Farm Bridge 1993

Environmental surveys:

- Archaeological Desk-Based Assessment, October 2019 (1)
- Archaeological Walkover Survey Addendum, June 2021 (v.1)
- Tree Constraints Plan-1476032
- Tree survey
- Burpham Court Farm fish bypass channel ecological report (Sept 2021)

Burpham Court Farm Arboricultural Impact Assessment

Previous FRAP docs:

- Burpham FRAP TMP RAMS & EMP
- Burpham FRAP Part A
- Burpham FRAP Part B10
- Burpham FRAP Part F3
- Red Line Boundary & Design
- Appendix I Flood Risk Assessment (in 'Designer's docs)
- Flood Risk Appendix A_Burpham_Technical Note v1.0 (in 'Designer's docs)
- Flood Risk Appendix B_Burpham_Hydraulic modelling summary_v1.0 (in 'Designer's docs)
- Burpham Court Farm fish bypass channel ecological report (Sept 2021) (in 'Environmental surveys)

Tree Constraints Plan-1476032 (in 'Environmental surveys)

Ground investigations:

- GI in info in WWT SUR02-2-K Concept Design Report (pages 18, 32-34 only)

6 photos of GI

Planning app docs/drawings:

23/D/00054 | Discharge of conditions 3 (construction phasing and protection measure scheme) and 4 (construction transport management plan) of planning permission 22/P/00881, approved on 16/11/2022. | Burpham Court Farm, Clay Lane, Jacobs Well (guildford.gov.uk)

23/D/00054 | Discharge of conditions 3, including:

METHOD STATEMENT & RISK ASSESSMENT C3085 - Thames Water interface

23_D_00054-CONSTRUCTION_TRANSPORT_MANAGEMENT_PLAN-1792085

23_D_00054-SITE_TRAFFIC_MANAGEMENT_PLAN-1792088

22/P/00881 | Construction of a naturalised fish bypass channel, incorporating three backwater features, an inlet structure (also serving as a crossing point), a formal crossing over a Thames Water sewer pipe and an informal rock ramp structure, along with construction of an earth bund along the boundary with Clay Lane. | Burpham Court Farm, Clay Lane, Jacobs Well (guildford.gov.uk)

22/P/00881, including:

- 22_P_00881-METHOD_STATEMENT___RISK_ASSESSMENT-1712222
- 22_P_00881-ARCHAEOLOGICAL_EVALUATION_REPORT-1712225
- 22_P_00881-ENVIRONMENTAL_MANAGEMENT_PLAN-1712229
- 22_P_00881-LAND_AND_WATER_SERVICES_ENVIRONMENTAL_MANAGEMENT_PLAN-1707968
- 22_P_00881-GENERAL_ARRANGEMENT_PLAN-1677748
- 22_P_00881-LANDSCAPE_AND_ECOLOGICAL_MANAGEMENT_PLAN-1677749
- 22_P_00881-LOCATION_PLAN_-_RED_LINE_BOUNDARY-1677750
- 22_P_00881-GENERAL_ARRANGEMENT_OF_FISH_PASS_EXIT_STRUCTURE-1677765
- 22_P_00881-FISH_PASS_EXIT_STRUCTURE_WALKWAY_ARRANGEMENT-1677769
- 22_P_00881-ECOLOGICAL_SURVEY_REPORT-1677735

Services search pack, including the following:

- Utility search request_Burpham Court Farm
- Site map
- Results Schedule
- LSBUD
- At a glance
- SGN
- UK Power Networks
- National Grid
- BT
- Cityfibre
- Vodafone
- Zayo
- CA Telecom
- Instalcom
- Sky
- Verizon
- Virgin Media
- Thames Water clean water

- Thames Water – waste water

River obstructions

240724-1.3-WSSANG-TPP-NC – Updated tree plan from Guildford Borough Council in regard to their Suitable Alternative Natural Greenspace construction.

Proposed sub-contractors				
	Name and address of proposed subcontractor	Nature and extent of work		
1.				
	Form of Contract:			
2.				
	Form of Contract:			
3.	Form of Contract:			
4.				
	Form of Contract:			