

TENDER CLARIFICATIONS

Query	Date	Response	Date
<p>We have a couple of queries regarding the proposed Drawings/Schedule of Works and have been instructed to contact you in the first instance. We refer to Schedule items 2.06 & 2.07, 3.02 & 3.03, 12.11 & 12.12, 16.07 & 16.08, 18.508, 18.509 and 18.605 & 18.606.</p> <p>1 All of the above refer to areas which require Joists, with OSB or Ply Decking over.</p> <p>Whilst the first 3 items are clearly shown on the Drawings, the item of the Stairs/Fire Escape is unclear as to how many floors are to be allowed for.</p>	06/08/2021	<p>Stairs ES1 - no change. Stair 2 (labelled G12 at ground floor, S2 at first floor and S3 at second floor) is 3 storeys in height but only one ceiling requiring joists with OSB and ply over. Stair structure and intermediate landings are to be proprietary steel stairs</p>	11/08/2021
<p>Also, the last two items, (i.e. New Mezz. Floor Mess Room M01 and new Mezz, Floor Locker Room do not appear to be indicated on any Drawings.</p>	06/08/2021	<p>Additional Mezzanine and Mess room M01 etc. are part of the 'Mezzanine Option' shown on drawing 605b-WD-10-011 within the folder '18 - Mezzanine Option'. The relevant area is boxed in red.</p>	11/08/2021