STAGE OUTPUTS AND DELIVERABLES

The expected Multi-Disciplinary Design Team outputs for the project are detailed below.

The following outputs are repeated for all stages:

- Stage programme with WBS.
- Progress and KPI performance reports (monthly).
- Contribution to Risk Register, Risk Management and Mitigation
- Contribution to Value Management plan.
- Contribution to Cost Plan.
- All relevant information / drawings uploaded to the Employer's Electronic Document and Record Management System/ Project Extranet (this will be in place from RIBA Stage 3 onwards)
- End of Stage Report.
- Design Meeting Schedule (regularly reviewed and updated).
- Employer Meeting Schedule (regularly reviewed and updated).
- Agendas and Minutes for Design Meetings (issue within 2 working days of meeting).
- Contribution to Agendas for Employer Meetings.

A summary of the Design Stage Specific Outputs is summarised below for reference.

MULTI-DISCIPLINARY DESIGN TEAM STRUCTURE

GC Works Stage	RIBA Stage	Expected Outputs / Deliverables
Stage 1 – Covering Inception of the Project	1	 Appraisal / Preparation: Draft Options Report (5 options to be provided with initial design concepts as defined in RFP). Review of existing brief and report. Contribution to / agreement of KPIs. BIM Specification. BIM Inputs and Outputs Design Brief: Final Options Report (with developed design concepts and recommended Option). Contribution to Procurement Strategy. Review report of existing Ground Investigation survey information – to include identification of gaps / recommended additional surveys. Initial Logistics/ Circulation Strategy for the site and facility. Initial Phasing Plan. Initial Bio-security and Biosafety Report. Initial Sustainability Strategy. Initial Security Strategy. Initial Facilities Management Strategy. Initial Landscape Strategy. Initial Site Waste Disposal Report. Initial Building Control Report. Draft Fire Strategy. Draft DDA Report. BIM data drop 1. End Stage Report.
	2	 Concept Design: Concept Design of chosen Option – to include design team drawings and report for Employer sign-off. Outline proposals for structural and building services systems and outline specifications. Draft of Planning Permission Application. BIM data for environmental performance and area analysis. Key BIM model elements and concept level parametric objects. Initial BREEAM assessment. Initial Room Data Sheets. Draft Logistics/ Circulation Strategy for the site and facility. Draft Phasing Plan. Draft Bio-Security and Biosafety Report. Draft Sustainability Strategy. Draft Security Strategy. Draft Facilities Management Strategy. Draft Landscape Strategy. Draft Site Waste Disposal Report. Draft Building Control Report. Revised Fire Strategy. Revised DDA Report. BIM data drop 2.
Stage 2 & 3 – Covering the	3	Developed Design: Detailed Concept Design of chosen Option – Report and coordinated drawings to include structural and building services systems and

MULTI-DISCIPLINARY DESIGN TEAM STRUCTURE

	1	
development		updated outline specifications for development into robust set of
of the design,		Employers Requirements.
preparation of		Detailed Planning Permission Application.
tender		Contribution to Whole Life Cost information
documents		BIM data for Detailed Planning Permission Application.
documents		4D or 5D BIM Assessment
		Revised BREEAM assessment.
		Revised Room Data Sheets. Project I project to Circulation Streets and facility.
		Revised Logistics/ Circulation Strategy for the site and facility.
		Revised Phasing Plan.
		Revised Bio-Security and Biosafety Report.
		Revised Sustainability Strategy.
		Revised Security Strategy.
		Revised Facilities Management Strategy.
		Revised Landscape Strategy.
		Revised Site Waste Disposal Report.
		Revised Building Control Report.
		Final Fire Strategy.
		Final DDA Report.
		Technical Design:
		Technical design(s) and performance specifications, sufficient to co-
		ordinate components and elements of the project.
		Information for statutory standards and construction safety.
		Contribution to Whole Life Cost information.
		Revised BREEAM assessment.
		Final Room Data Sheets.
		Final Logistics/ Circulation Strategy for the site and facility.
		Final Phasing Plan.
	4	=
		Final Bio-Security and Biosafety Report. Final Operation Hills Observed. Final Operation of Hills Observed.
		Final Sustainability Strategy.
		Final Security Strategy.
		Final Facilities Management Strategy.
		Final Landscape Strategy.
		Final Site Waste Disposal Report.
		Final Building Control Report.
		BIM data drop 3.
		·
		Tender Documentation:
		Preparation of Employers Requirements in sufficient detail to enable
		a tender or tenders to be obtained.
		Application for statutory approvals.
		Preparation of further information for construction required under the
		building contract.
		Contribution to Whole Life Cost information.
	der	BIM data drop 4.
	Tender	
	-	Tender Action:
		Contribution to identification and evaluation of potential contractors
		and/or specialists for the project.
		Contribution to submission of recommendations to the Employer.
		Contribution to appraising tenders.
		Technical appraisal of contractor's tender proposals.
Stage 4 & 5 –		Construction:
Covering the	5 - 7	Contribution to issuing of information to the contractor.
construction		End of Construction BIM record model data.
	1	

MULTI-DISCIPLINARY DESIGN TEAM STRUCTURE

JIC - NGI TEAM

and operations on site, and	 BIM data drop 5. Contribution to Agendas for Employer Meetings. Contribution to Lessons Learned Workshop and Report.
completion	