








<h1 style="text-align: center;">SAFETY HEALTH &amp; ENVIRONMENTAL INFORMATION</h1>	
<p>In addition to the hazards/risks normally associated with the type of work detailed on this drawing, note the following risks and information.</p> <p>Risks listed here are not exhaustive. Refer to Designer's Risk Assessment and pre-construction phase plan.</p>	
<h2>CONSTRUCTION</h2>	
	<p><b>Managing flow &amp; stage levels in River Fowey</b></p> <ul style="list-style-type: none"> <li>- Monitor flow levels &amp; flood warnings.</li> <li>- Check adequacy of cut-off &amp; stability of cofferdams.</li> </ul>
	<p><b>Managing seepage flows through weir</b></p> <ul style="list-style-type: none"> <li>- Monitor seepage.</li> <li>- Check stability of cut face in weir and assess permeability of formation material.</li> <li>- Check adequacy of cut-off &amp; stability of cofferdams.</li> </ul>
	<p><b>Risk of falls from height</b></p> <ul style="list-style-type: none"> <li>- Check depth of excavations.</li> <li>- Check adequate edge protection and access provision onto weir.</li> </ul>
	<p><b>Lifting</b></p> <ul style="list-style-type: none"> <li>- Check craneage lifting facilities &amp; constraints.</li> <li>- Check access weight &amp; size restrictions for craneage at bridge crossings along access route to site.</li> </ul>
	<p><b>Interface with public &amp; other site operations</b></p> <ul style="list-style-type: none"> <li>- Check adequate warning signs and fencing in place.</li> </ul>
	<p><b>Services</b></p> <ul style="list-style-type: none"> <li>- Check for services.</li> </ul>
	<p><b>Stability of Excavations &amp; Structures and Banks</b></p> <ul style="list-style-type: none"> <li>- Carry out inspection pits to check weir construction &amp; depth to footings for adjoining abutment wall.</li> <li>- Check temporary works &amp; construction sequencing to maintaining structural integrity of weir and stability of adjacent abutment wall.</li> </ul>
<h2>OPERATION &amp; MAINTENANCE</h2>	
<p>For information relating to Use, Cleaning and Maintenance see the Health and Safety File</p>	
<p>It is assumed that all works will be carried out by a competent contractor working, where appropriate, to an approved method statement</p>	

**101 / 01 - Proposed Works - General Arrangement**  
1:25