

CONSTRUCTION NOTES

Clear weeds from whole area of car park.
 Break up, remove and cart away existing macadam paving.
 Excavate to reduce levels, over 270mm, grade and consolidate ground and cart away excess spoil.
 Supply and fit 450mm dia trapped road gullies with Wekin Tri-Star Ductile Iron Gully Gate, 430x370 - D400, 1000dia pipe laid to falls to 4m3 Aquacell soakaway.
 Supply and lay MOT type 1 sub-base, 150mm thick to whole area of car park, final stopped and consolidated to level formation to falls and cross falls.
 Supply and fit 150mm x 50mm pre-cast concrete edgings and concrete base with suitable haunching to perimeter of new paved area as shown on plan. Top of edgings flush with finished paved surface.
 Supply and lay 80mm thickness of 20mm size dense binder course, group 6.5, to falls and cross falls to new car park area.
 Supply and lay 40mm thickness of 10mm size stone mastic surface course, group 6.5, to falls and cross falls to new car park area.
 Mark out parking bays etc with white thermoplastic paint.
 Fair flush finishings to all adjacent areas.
 Site to be left clean & tidy on completion.

Key

-  **OPTION 1**
New Macadam paved surface to whole area of car park including road gullies RG1-RG3
-  **OPTION 2**
Alternative surface:
Self draining Ecogrid 40 plastic grids [omit RG3]

New 4m3 Aquacell soakaway with geotextile cover. Reinstate grassed area

Playing Field



Proposed External Works at Water Orton Playing Field Pavilion at Water Orton Croft, Water Orton, for Water Orton Parish Council

Proposed Plan

Scale. 1:100 @ A3
 Date. August 2019

1330-02



No 4 Openfield Croft