



- 1) Resurfacing works
- 2) Refresh all the directional lining markings
- 3) Remove all debris from 6 surface water gullies and dispose of all waste. Also jet clean the pipelines.
- 4) Repatching and overbanding 1m2 x2No
- 5) Replace 5No existing bollards (4 in front of main entrance and 2 at the rear)
- 6) Introduce 4No 5mph speed limit signs as directed by engineer

Replace existing 6 lockable bollards at main and rear entrance

2 x1m2 of repatching and overbanding

14m x 1m (14 m2) of 40mm resurfacing and overbanding

## Municipal Offices Car Park Plan

### Surfacing and Minor Civil Works 2021

Department:	Env Care Services
Paper Size:	A4
Drawing No:	2020.12.14_05
Date:	15/12/2020
Scale:	1:700