- This drawing is copyright and may not be altered, traced, copied, photographed or used for any purpose other than that for which it is issued without written permission from Meiloci Landscape Architects.
- Do not scale for construction purposes. Figured dimensions shall have precedence over scaled dimensions.
- Any discrepancies should be reported to the Landscape Architect.
- All trees and hedgerows are to be protected in accordance with BS5837 and/or Arboricultural recomendations unless instructed otherwise.

NOTES / REVISIONS

REV.	DESCRIPTION	INIT.	DATE
01	Draft issue	GS	31-01-24
02	Tree planting updated (3 trees added)	GS	06-02-24
03	Sensory planting added, tender issue	GS	07-02-24

Tree and Edible Scrub Planting

Trees

Number	Species	Common Name	Girth	Height	Specification
3	Amalanchier arborea 'Robin hill'	June berry	8-10cm	2.5-3.0m	2x :Standard :Clear Stem 175-200 :3 brks :RB
1	Apple 'Bens Red'			1.0-1.5m	X/1/0; Maiden; MM106 rootstock :BR
1	Apple 'Bramley'			1.0-1.5m	X/1/0; Maiden; MM106 rootstock :BR
1	Apple 'Cornish Gilliflower'	Apple (Cornish variety)		1.0-1.5m	X/1/0; Maiden; MM106 rootstock :BR
1	Apple 'Cornish Pine'	Apple (Cornish Variety)		1.0-1.5m	X/1/0; Maiden; MM106 rootstock :BR
1	Apple 'Golden Noble'	Cornish Apple		1.0-1.5m	X/1/0; Maiden; MM106 rootstock :BR
1	Apple 'Pig Nose'			1.0-1.5m	X/1/0; Maiden; MM106 rootstock :BR
1	Apple 'Strawberry Pippin'	Cornish Apple		1.0-1.5m	X/1/0; Maiden; MM106 rootstock :BR
1	Apple 'Tregonna King'	Tregonna King		1.0-1.5m	X/1/0; Maiden; MM106 rootstock :BR
2	Cornus florida		8-10cm	2.5-3.0m	2x :Standard :Clear Stem 175-200 :3 brks :RB
3	Crataegus prunifolia 'Splendens'		8-10cm	2.5-3.0m	2x :Standard :Clear Stem 175-200 :3 brks :RB
10	Ulmus Vada ("Wanoux")	Elm "Vada"	8-10cm	2.5-3.0m	2x :Standard :Clear Stem 175-200 :3 brks :RB

Edible scrub

Number	Species	Common Name	Height	Specification	Density
30	Blackcurrant 'Ben Connan'		60-80cm	0/1; Cutting; branched; 3 breaks :BR	0.8Ctr
30	Blackcurrant 'Ben Lomond'		60-80cm	0/1; Cutting; branched; 3 breaks :BR	0.8Ctr
59	Corylus avellana 'Cosford Cob'		100-125cm	3 breaks :BR	0.8Ctr
59	Corylus avellana 'Webb's Prize Cobb'		100-125cm	3 breaks :BR	0.8Ctr
30	Gooseberry 'Hinnonmaki Red'		60-80cm	0/1; Cutting; branched; 3 breaks :BR	0.8Ctr
30	Gooseberry 'Whinham's Industry'		60-80cm	0/1; Cutting; branched; 3 breaks :BR	0.8Ctr
30	Mespilus germanica	Medlar	1.0-1.2m	Maiden :BR	0.8Ctr
59	Prunus domestica 'Kea'	Kea Plum (Cornish)	1.0-1.2m	X/1/0; Maiden; St Julian A rootstock; :BR	0.8Ctr
59	Prunus domestica 'Manaccan'	Manaccan plum (Cornish)	1.0-1.2m	X/1/0; Maiden; St Julian A rootstock; :BR	0.8Ctr
30	Prunus institia 'Damson'	Damson	80-100cm	1+1; Transplant :3 brks :BR	0.8Ctr
30	Redcurrant 'Junifer'		60-80cm	0/1; Cutting; branched; 3 breaks :BR	0.8Ctr
30	Redcurrant 'Laxtons No1'		60-80cm	0/1; Cutting; branched; 3 breaks :BR	0.8Ctr
59	Sambucus nigra	Common Elder	80-100cm	1+1; Transplant :3 brks :BR	0.8Ctr
30	Whitecurrant 'Blanka'		60-80cm	0/1; Cutting; branched; 3 breaks :BR	0.8Ctr
30	Whitecurrant 'White Versailles'		60-80cm	0/1; Cutting; branched; 3 breaks :BR	0.8Ctr

Total :595

Sensory Mix_Larger				
Number	Species	Pot Size	Specification	Density
23	Artemisia pontica	2L	Full Pot	0.45Ctr
12	Centaurea macrocephala	2L	Full Pot	0.45Ctr
12	Centaurea scabiosa	2L	Full Pot	0.45Ctr
23	Echinacea purpurea 'Magnus'	2L	Full Pot	0.45Ctr
23	Echinops ritro 'Veitch's Blue'	2L	Full Pot	0.45Ctr
23	Eryngium planum 'Blaukappe'	2L	Full Pot	0.45Ctr
12	Foeniculum vulgare 'Purpureum'	2L	Full Pot	0.45Ctr
12	Helenium 'Moerheim Beauty'	2L	Full Pot	0.45Ctr
12	Helianthus maximiliani	2L	Full Pot	0.45Ctr
23	Helichrysum italicum	2L	Bushy	0.45Ctr
12	Miscanthus nepalensis	2L	Full Pot	0.45Ctr
12	Miscanthus sinensis 'Malepartus'	2L	Full Pot	0.45Ctr
12	Verbascum 'Firedance'	2L	Full Pot	0.45Ctr
23	Verbena bonariensis	2L	Full Pot	0.45Ctr

Total :234

Sensory Mix_Larger_Reduced				
Number	Species	Pot Size	Specification	Density
4	Artemisia pontica	2L	Full Pot	0.45Ctr
4	Centaurea scabiosa	2L	Full Pot	0.45Ctr
4	Echinacea purpurea 'Magnus'	2L	Full Pot	0.45Ctr
4	Echinops ritro 'Veitch's Blue'	2L	Full Pot	0.45Ctr
4	Eryngium planum 'Blaukappe'	2L	Full Pot	0.45Ctr
4	Foeniculum vulgare 'Purpureum'	2L	Full Pot	0.45Ctr
4	Helichrysum italicum	2L	Bushy	0.45Ctr
4	Miscanthus sinensis 'Malepartus'	2L	Full Pot	0.45Ctr
4	Verbascum 'Firedance'	2L	Full Pot	0.45Ctr
4	Verbena bonariensis	2L	Full Pot	0.45Ctr

Total :40

Sensory Mix_Smaller				
Number	Species	Pot Size	Specification	Density
11	Achillea millefolium 'Red Velvet'	2L	Full Pot	0.35Ctr
21	Allium schoenoprasum	1.5-2L	Full Pot	0.35Ctr
21	Cenchrus alopecuroides 'Dark Desire'	2L	Full Pot	0.35Ctr
21	Chamaemelum nobile	1-1.5L	Full Pot	0.35Ctr
21	Cosmos atrosanguineus 'Chocamocha'	1.5-2L	Full Pot	0.35Ctr
11	Erigeron glaucus 'Sea Breeze'	1.5-2L	Full Pot	0.35Ctr
21	Knautia macedonica	2L	Full Pot	0.35Ctr
11	Salvia argentea	2L	Full Pot	0.35Ctr
11	Salvia officinalis 'Purpurascens'	1-1.5L	Full Pot	0.35Ctr
11	Santolina chamaecyparissus 'Lemon Queen'	2L	Bushy	0.35Ctr
21	Stachys byzantina	2L	Full Pot	0.35Ctr
21	Stipa tenuissima 'Pony Tails'	2L	Full Pot	0.35Ctr
11	Thymus serpyllum	1.5-2L	Full Pot	0.35Ctr

Total :213

01 / 4002 PLANTING PLAN
Scale 1: 200

Notes

- Allow for required soil depths and ground preparation as described and shown
- **Tree planting:** Allow for tree pit preparation and staking as described and shown
- **Edible scrub mix:** Currents and gooseberries to be arranged in same-variety groupings of 3 - 5 plants and arranged towards the front of the planting bed, with larger shrub/ tree sp. (e.g. damson, cobnut, plum) randomly mixed and planted to the back of the planting bed
- Bare root planting will only be available through dormant season (e.g. Nov - March). Program planting work accordingly.
- Take care not to damage high visibility geotextile (laid as part of remediation proposals) during planting operations

Key risks/ remaining hazards

- Heavy lifting of standard trees required - put in place suitable lifting procedures/ equipment to minimise risks

Key:

- grassed area - seeded
- wildflower meadow - seeded
- low growing amenity planting - planted with container grown shrubs/ perennials/ grasses
- sensory planting - planted with container grown shrubs/ perennials/ grasses
- edible scrub planting - planted with container grown/ bare root shrubs
- low Cornish hedge (wildflower topped)
- smaller species tree planting - planted as clear stemmed standards
- larger species tree planting - planted as clear stemmed standards
- fruit tree planting - planted as feathered maidens
- SuDS swale/ rain garden

MEI LOCI

Mei Loci Landscape Architects
67 Lemon Street, Truro, Cornwall, TR1 2PN
studio@meiloci.co.uk | 01872 264 899

CLIENT
Camborne Town Council

JOB DESCRIPTION/LOCATION
Kerrier Way Green Gateway
Camborne
Cornwall

DRAWING TITLE
Planting Plan -
Trees, Scrub, Sensory and Seeding

TENDER

Date	Scale	Drawn By	Checked
10.08.23	1:200	GS	PH
Job. No.	Drawing No.		Revision
M580	DR-L-4002		03