

Schedule of Repair Works Intermediate Level Repairs

2 SUPERSTRUCTURE

30.10.19
These items have been extracted from the condition survey produced by Aardman Associates Ltd, dated October 2017

Prices for these items are to be itemised separately from "Essential Works."

2.5 External Walls

- Replace porous stonework and rake out and repoint loose/missing mortar, with a lime based mortar to match existing, to west end of the south facing wall.
- Remove loose mortar, rake out and repoint loose/missing mortar, with a lime based mortar to match existing, to the east end of the north elevation.
- Replace porous stonework and rake out and repoint loose/missing mortar, with a lime based mortar to match existing, to the west facing gable above the Council chamber.