

**National Asset Delivery  
Technical Surveys and Testing**

**Scope for  
603429 - SWAD 2020 Tree Condition  
Surveys**

**Phase 1:**

**A30 Cornwall (Longrock to Dunheved Bridge)**

**and**

**A30 Devon (Dunheved Bridge to Exeter)**



**TABLE OF CONTENTS**

<b>1</b>	<b>PURPOSE OF THE <i>SERVICES</i></b> .....	<b>4</b>
<b>2</b>	<b>EXISTING INFORMATION</b> .....	<b>5</b>
<b>3</b>	<b>CONSTRAINTS ON HOW THE CONSULTANT PROVIDES THE <i>SERVICES</i></b> ..	<b>6</b>
<b>4</b>	<b>REQUIREMENTS FOR THE PROGRAMME</b> .....	<b>9</b>
<b>5</b>	<b>SERVICES AND OTHER THINGS PROVIDED BY THE <i>CLIENT</i></b> .....	<b>12</b>
<b>6</b>	<b>SPECIFICATION FOR THE <i>SERVICES</i></b> .....	<b>13</b>

**LIST OF ANNEXES**

Appendix 1 **Supplementary Constraints**

FOR INFORMATION ONLY  
DO NOT COMPLETE AT THIS STAGE

## 1 PURPOSE OF THE SERVICES

### 1.1 Project objectives

- 1.1.1 The principle objective of this project is to undertake and report on the condition inspection and survey of highway trees for the specified lengths of Strategic Road Network (SRN), so discharging a duty upon Highways England to identify 'safety critical defects' and 'reactive defects' in the interest of maintaining a safe network.
- 1.1.2 The specification that applies to the *services* is included in Section 6. The survey and reporting should be undertaken in accordance with the 'Tree Condition Inspections / Surveys - Supply Chain Brief' for the 'SWAD 2020 Tree Condition Surveys Phase 1: A30 Cornwall (Longrock to Dunheved Bridge) and A30 Devon (Dunheved Bridge to Exeter)'.

### 1.2 Scope of services

- 1.2.1 The *services* to be provided under this contract are:
- (1) Arboricultural surveys as specified in the 'Tree Condition Inspections / Surveys - Supply Chain Brief' for the 'SWAD 2020 Tree Condition Surveys Phase 1: A30 Cornwall (Longrock to Dunheved Bridge) and A30 Devon (Dunheved Bridge to Exeter)'.

### 1.3 Deliverables

- 1.3.1 The *Consultant* is required to produce the following deliverables:
- (1) Separate reports should be produced for the two routes, as specified in the 'Tree Condition Inspections / Surveys - Supply Chain Brief' for the 'SWAD 2020 Tree Condition Surveys Phase 1: A30 Cornwall (Longrock to Dunheved Bridge) and A30 Devon (Dunheved Bridge to Exeter)'. One entitled "Highways England SWAD 2020 Tree Condition Surveys - Phase 1: A30 Cornwall (Longrock to Dunheved Bridge)", and the other "Highways England SWAD 2020 Tree Condition Surveys - Phase 1: A30 Devon (Dunheved Bridge to Exeter)". Contents of each report must include but is not limited to a brief introduction, scope, methodology, survey limitations, a brief summary of the survey findings, survey results in the form of summary tables, and overview plans of the route showing tree locations referenced to the summary tables. The overview plans and 'Tree Survey Sheets' (refer to the 'Supply Chain Brief' for content on these) must be presented in appendices. The summary tables, overview plans and 'Tree Survey Sheets' must separate carriageway direction and be presented in the direction of travel, adopting the convention that the first direction reported is implicit in the survey title.

## 2 EXISTING INFORMATION

- 2.1.1 This inspection / survey requires knowledge of the Highways England operational estate. The extent of the estate is being continuously revised following delivery of improvement schemes, land transactions or receipt of new information, and should therefore be taken from the latest base layer of EnvIS (Highways England Environmental Information System). The soft estate layer and road marker post layer are provided with this tender package as GIS layer file attachments contained within an email specific to each route.
- 2.1.2 The Highways England [GeoStore](#) website enables the *Consultant* to request and download OS base mapping to assist with reporting for this project, subject to registration and approval on application for specific data. Details will be provided to the *Consultant*.
- 2.1.3 The Highways England 'South West Network Induction' is available to support the *Consultant* with their staff induction.

FOR INFORMATION ONLY  
DO NOT COMPLETE AT THIS STAGE

### **3 CONSTRAINTS ON HOW THE CONSULTANT PROVIDES THE SERVICES**

#### **3.1 General**

- 3.1.1 The *Consultant* Provides the Services in such manner as to minimise the risk of damage or disturbance to or destruction of third party property.
- 3.1.2 The *Consultant* complies with the constraints and meets with the requirements outlined in Appendix 1.
- 3.1.3 The *Consultant* submits information detailing how the *Consultant* will provide the Services to the *Client* prior to the *services* commencing. This information will include any lifting plans, risk assessments, method statements, the *Consultant's* staff training information and any other relevant Health and Safety requirements.

#### **3.2 Working hours & site specific constraints**

- 3.2.1 The *Consultant's* working hours for site works shall be daylight hours unless agreed otherwise with the Highways England Technical Surveys Manager.
- 3.2.2 The *Consultant* is responsible to ensure that all field staff are appropriately inducted by a competent person on all aspects of activities required by the brief. The Highways England 'South West Network Induction' is available to support the *Consultant* with their staff induction. Evidence of staff induction is required.
- 3.2.3 The *Consultant* must have in place Safe Systems of Work, Risk Assessments and a Method Statement that are specific to the activities proposed. These should be provided to the Highways England Technical Surveys Manager for review prior to any site activity. Refer to the 'Tree Condition Inspections / Surveys - Supply Chain Brief' for contact details.
- 3.2.4 The *Consultant* must place and be competent to place 'Surveying' signs on the network where field staff are visible to road users for periods exceeding 15 minutes. Such signs are considered to be information signs, not instruction signs, therefore the persons) placing them do not require Chapter 8 sector scheme certification. Signs should be placed 1.2m away from traffic and facing oncoming traffic.
- 3.2.5 If stopping or parking in the verge or a maintenance hard standing space, the survey vehicle must be marked up appropriately for Highways Maintenance (Chapter 8 compliant). If an unmarked private vehicle is used, it may only be used in the same way as any other road user (i.e. no stopping or parking on the verge, no parking within maintenance hard standings).

- 3.2.6 Some stretches of the A30, particularly through Cornwall, may require temporary traffic management to safely inspect / survey the trees. These road lengths will need to be identified by the *Consultant* early on and details provided to the Highways England Technical Surveys Manager at [SWSurveys@highwaysengland.co.uk](mailto:SWSurveys@highwaysengland.co.uk).
- 3.2.7 Traffic management and road space booking will be arranged by the Highways England Technical Surveys Manager and provided by Highways England supply chain at no cost to the *Consultant*. Some 4 to 6 weeks is usually required to make the necessary arrangements for traffic management and it is subject to road space being available. The provider of traffic management would become Principal Contractor for these elements of the survey and their safety requirements will need to be complied with.
- 3.2.8 It is a requirement that all persons working on the Highways England network wear high visibility long sleeved yellow jackets and trousers, and protective footwear at all times. Other personal protective equipment identified in the supply chain Risk Assessment must also be worn as and when appropriate.
- 3.2.9 It is prohibited to cross any live Highways England carriageway on foot, including slip lanes up to the node point where the Highways England network switches to County road. Crossing a live County road is not prohibited.
- 3.2.10 The Regional Operations Centre must be advised in advance of accessing the network, then at arrival on site and finally on departure from site.
- 3.2.11 No access should be made onto private land without prior consent of the landowner / tenant / occupier.

### 3.3 Health, Safety and Environment & Risk Management

#### Health and Safety requirements

- 3.3.1 In Providing the Services the *Consultant* meets the requirements of Annex 2 of the supplementary constraints relation to health and safety duties. The *Consultant* also adheres to the requirements in Section 3.2 above.
- 3.3.2 When implemented, the *Consultant* shall comply with the requirements of Highways England's safety passport scheme and ensure that all of his employees, and any of his subcontractor's, are registered in accordance with the implementation of the scheme.
- 3.3.3 Before commencing the construction phase of the *services*, the *Consultant* confirms to the *Client* that adequate welfare facilities are in place. Where the facilities detailed in section 5 are not deemed adequate, the *Consultant*

provides all necessary facilities to Provide the Services and to comply with the minimum requirements set out in HSE guidance document L153.

#### Environmental requirements

- 3.3.4 In Providing the Services the *Consultant* meets the requirements of Annex 2 of the supplementary constraints in relation to environmental duties.

#### Risk Management

- 3.3.5 The *Consultant* identifies, manages and mitigates risks in accordance with the principles of ISO31000.
- 3.3.6 The *Consultant* submits a risk register, which captures all risks associated with the delivery of the services including those identified by the *Client*, with his tender and maintains it for the contract period.

FOR INFORMATION ONLY  
DO NOT COMPLETE AT THIS STAGE

## 4 REQUIREMENTS FOR THE PROGRAMME

4.1.1 The *Consultant* submits programme to the *Client* with his tender.

4.1.2 The *Consultant* Provides the Services taking into account the following programme constraints:

- (i) the *starting date*, - which will be 1<sup>st</sup> July 2020.
- (ii) *Start-up meeting* – to be held at Highways England Ash House office, Exeter, within 2 weeks of the tender award.
- (iii) *completion date*, - field surveys to be complete by 25<sup>th</sup> September 2020; final survey reports to be submitted by no later than 2<sup>nd</sup> November 2020.
- (iv) and any post site works, - n/a
- (v) reporting and review period - draft reports to be provided by no later than 12<sup>th</sup> October 2020; Highways England Environmental Manager will review and return comments by 21<sup>st</sup> October 2020; final reports are required by no later than 2<sup>nd</sup> November 2020.
- (vi) The services and other things provided by *Client* (see Section 5)
- (vii) The *Consultant* is responsible to ensure that all field staff are appropriately inducted by a competent person on all aspects of activities required by the brief. The Highways England 'South West Network Induction' is available to support the *Consultant* with their induction. Evidence of staff induction is required.
- (viii) The *Consultant* must have in place Safe Systems of Work, Risk Assessments and a Method Statement that are specific to the activities proposed. These should be provided to the Highways England Technical Surveys Manager for review prior to any site activity.
- (ix) Safety Critical Defects – the *Consultant* must provide details immediately to the Regional Operations Centre, and advise the Highways England Environmental Manager at soonest opportunity.
- (x) High Priority Reactive Defects – the *Consultant* must provide details weekly to the Highways England Service Manager, copied to the Highways England Environmental Manager.
- (xi) As the survey progresses the *Consultant* must inform the Highways England Environmental Manager fortnightly of percentage completion along each route.
- (xii) The *Consultant* must provide a monthly summary of all defects by route to the Highways England Environmental Manager, and then a final summary on completing the survey of each route.

- (xiii) The *Consultant* must prepare separate reports for the two routes. One entitled “Highways England SWAD 2020 Tree Condition Surveys - Phase 1: 30 Cornwall (Longrock to Dunheved Bridge)”, and the other “Highways England SWAD 2020 Tree Condition Surveys - Phase 1: A30 Devon (Dunheved Bridge to Exeter)”. These should be submitted to the Highways England Environmental Manager in draft by 12<sup>th</sup> October 2020.
- (xiv) Comments on the draft reports will be returned to the *Consultant* by 21<sup>st</sup> October 2020 and one report review meeting at the Highways England Ash House office in Exeter should be programmed prior to issue of the final reports. This would require attendance by the report author(s) and Highways England Environmental Manager. Final reports are required to be submitted to the Highways England Environmental Manager by no later than 2<sup>nd</sup> November 2020.
- (xv) One hard copy and an electronic copy of each final report should be issued to the Highways England Environmental Manager. An unlocked Excel spreadsheet of the summary tables presented in each report should also be provided, so Highways England can develop the necessary follow up actions. All information obtained and issued in delivery of these surveys will become the property of Highways England and may be stored or used by Highways England or its agents for the purpose of managing the Strategic Road Network.
- 4.1.3 The programme should be in the form of an activity and time related bar chart, produced as a result of a critical path analysis.
- 4.1.4 The programme should preferably be provided in either a PDF or MS Excel format and cover the full contract period including post site activities. Activities should be clearly defined and named and the programme should detail the following:
- (i) dates and times associated with the project, including the *starting date*, *completion date* & *Consultant’s* planned completion, and any other dates or times that will specifically impact the delivery of the project.
  - (ii) activities associated with delivering the project, to include start-up meeting, mobilisation period, field survey, reporting, report review meeting.
  - (iii) draft report submission;
  - (iv) draft report review period;
  - (v) final report submission.

- 4.1.5 The *Consultant* should provide details of the proposed resources (plant, labour, subcontractors etc.) expected to deliver each activity. This information can either be shown on the programme itself or provided in an associated resource statement included in the Proposal for Providing the Services.
- 4.1.6 The *Consultant* updates the programme every four weeks. The *Consultant* submits an updated programme to the *Client* upon request.

FOR INFORMATION ONLY  
DO NOT COMPLETE AT THIS STAGE

**5 SERVICES AND OTHER THINGS PROVIDED BY THE CLIENT**

- 5.1.1 The *Client* does not provide anything with respect to Traffic Management, unless requested by the *Consultant*. Refer paras 3.2.6 and 3.2.7.
- 5.1.2 'Not used'.
- 5.1.3 The other things that will be provided by the *Client* are as follows:
- (1) Refer to Section 2.

FOR INFORMATION ONLY  
DO NOT COMPLETE AT THIS STAGE

## 6 SPECIFICATION FOR THE SERVICES

6.1.1 The *Consultant* shall Provide the Services in accordance with:

- The attached 'Tree Condition Inspection / Surveys - Supply Chain Brief' for the 'SWAD 2020 Tree Condition Surveys Phase 1: A30 Cornwall (Longrock to Dunheved Bridge) and A30 Devon (Dunheved Bridge to Exeter)'.

FOR INFORMATION ONLY  
DO NOT COMPLETE AT THIS STAGE