







TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.01	<p>Redundant Deck Fittings.</p>  <p>Numerous vehicle deck deck fittings are excessively corroded. As no longer required, they are to be removed and any areas of corroded plate cropped out and weld inserts fitted, REPRESENT affected areas. ALLOW for 50 in number fittings. ALLOW for 30m² REPRESENTATION</p>	<p>Hotwork Required – Appropriate precautions to be taken iaw General 8.4.</p> <p>Iaw Paint scheme -General 12 and Annex B refer.</p>


TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.02	<p>Redundant vehicle deck tie-down points.</p>  <p>Clear out heavily corroded redundant vehicle deck tie down points and resin fill. REPRESENT area on completion. ALLOW for 50 tie down points and 20m² REPRESENTATION.</p>	IAW Paint scheme - General 12 and Annex B refer.


TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.03	<p>Tank Vent Goose Necks</p>  <p>Numerous tank vent Goose Necks are have suffered excessive corrosion such that full thickness penetration is evident and some have come detached from deck. Manufacture and RENEW goosenecks affected. Goosenecks are welded to deck. REPRESENT goosenecks and deck area on completion.</p> <p>ALLOW for 10 goose necks. ALLOW for 15m² REPRESENTATION.</p>	<p>Hotwork Required – Appropriate precautions to be taken iaw General 8.4.</p> <p>IAW Paint scheme -General 12 and Annex B refer.</p>


TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.04	<p>Deck Drain Opening</p>  <p>Forecastle deck drain port side has grill missing allowing ingress of debris and is heavily corroded. Prove drain clear and unblock as necessary. RENEW grill studs, REPRESENT deck drain opening and surrounding deck area. Supply and fit new deck drain grill.</p> <p>ALLOW for 1m² REPRESENTATION.</p>	<p>Hotwork Required – Appropriate precautions to be taken iaw General 8.4.</p> <p>IAW Paint scheme -General 12 and Annex B refer.</p>


TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.05	<p>Forecastle Deck Fittings</p>  <p>Numerous unused Forecastle deck fittings are excessively corroded and beyond preservation. Fittings to be removed and deck area REPRESENTED on completion. Fittings to be identified to contractor by Authority's Authorised Representative. Contractor to dispose of redundant fittings.</p> <p>ALLOW for 10 in number fittings. ALLOW for 5m² REPRESENTATION.</p>	<p>Hotwork Required – Appropriate precautions to be taken iaw General 8.4.</p> <p>IAW Paint scheme -General 12 and Annex B refer.</p>

TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.06	<p>Hawse Pipes</p>  <p>There is evidence of pitting within the port and stbd hawse pipes.</p> <p>Abrade back and NDE to determine remaining wall thickness. To be at least 2/3 original thickness in areas in contact with chain or anchor, else 4mm is adequate to retain watertight integrity (original fitted thickness may be estimated based on thickness measurement of uncorroded area). REPRESENTATION on completion.</p> <p>ALLOW for 15m² REPRESENTATION.</p>	<p>NDE Required</p> <p>IAW Paint scheme - General 12 and Annex B refer.</p>


TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.07	<p>Hawse Pipe Grill</p>  <p>The stbd hawse pipe grill has cut-out for cable however cable not fitted on stbd side leaving unnecessary opening on deck. Existing grill to be RENEWED with one that covers entire hawse pipe opening. REPRESENTATIVE securing brackets on completion.</p> <p>ALLOW for 2m² REPRESENTATION.</p>	<p>Hotwork Required – Appropriate precautions to be taken iaw General 8.4.</p> <p>To be done in conjunction with H2.06.</p> <p>IAW Paint scheme - General 12 and Annex B refer.</p>


TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.08	<p>Foremast Wire Stays</p>  <p>The 3 in number foremast cable stays are showing galvanising breakdown and corrosion. RENEW 3 in number cable stays and REPRESENT anchor points.</p> <p>ALLOW for 3m² REPRESENTATION.</p>	<p>IAW Paint scheme - General 12 and Annex B refer.</p>


TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.09	<p>Redundant Fire Hydrants</p>  <p>All fire hydrants now redundant, pipework heavily corroded with no paint coatings remaining and with wall thickness severely reduced. REMOVE hydrants (x5) and weld blanks in place to cover deck penetrations. REPRESENT on completion.</p> <p>ALLOW for 5m² REPRESENTATION.</p>	<p>Hotwork Required – Appropriate precautions to be taken iaw General 8.4.</p> <p>IAW Paint scheme -General 12 and Annex B refer.</p>


TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.10	<p>Redundant Accommodation Ladder Davit</p>  <p>Active corrosion and paint coating breakdown at base of redundant accommodation ladder davit. Davit no longer used therefore davit to be REMOVED and deck area REPRESENTED. Contractor to dispose of all removed materials on completion.</p> <p>ALLOW for 1m² REPRESENTATION.</p>	<p>Hotwork Required – Appropriate precautions to be taken iaw General 8.4.</p> <p>To be completed in conjunction with H2.17</p> <p>IAW Paint scheme - General 12 and Annex B refer.</p>

TASK NO.	TASK/DESCRIPTION		NOTES
	H2	HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.11	<p>02 Deck</p> <div data-bbox="400 465 746 1068" data-label="Image"> </div> <div data-bbox="767 477 1104 1068" data-label="Image"> </div> <p>Port and stbd 02 deck waist decks have had deck screeding removed and are heavily corroded. Decks to be REPRESENTED with non slip paint coating.</p> <p>ALLOW for 80m² REPRESENTATION.</p>		<p>IAW Paint scheme - General 12 and Annex B refer.</p> <p>To be completed in conjunction with H3.04.</p>


TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.12	<p>Gundeck Aerial Boxes</p>  <p>Port and stbd aerial mounting boxes have corroded to the extent aials have now become detached. Aerials are redundant. Remove both mounting boxes and PRESERVE affected area. Contractor to dispose of removed items.</p> <p>ALLOW for 2m² PRESERVATION.</p>	<p>Hotwork Required – Appropriate precautions to be taken iaw General 8.4.</p> <p>IAW Paint scheme -General 12 and Annex B refer.</p>


TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.13	<p>Flight Deck Paint Coating</p>  <p>The flight deck has many areas of paint coating breakdown leading to active corrosion of the deck. Carry out patch repair PRESERVATION.</p> <p>ALLOW for 25m². PRESERVATION.</p>	<p>IAW Paint scheme -General 12 and Annex B refer.</p> <p>To be completed in conjunction with H2.14.</p>


TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.14	<p>Flight Deck Monitors</p>  <p>Both flight deck monitors are redundant, and excessive pipe corrosion has resulted in them becoming detached from the deck. Contractor to dispose of both monitors, cut remaining pipework to deck level and weld blanks in place. REPRESENT on completion.</p> <p>ALLOW for 2m² REPRESENTATION.</p>	<p>Hotwork Required – Appropriate precautions to be taken iaw General 8.4.</p> <p>IAW Paint scheme -General 12 and Annex B refer.</p> <p>To be completed in conjunction with H2.13.</p>


TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.15	<p>Port and Stbd Bridge Wing Decks</p>  <p>Port and stbd Bridge Wing decks have large areas of paint coating breakdown and active corrosion present. REPRESENT deck coatings. Allow for 30m² total. REPRESENTATION.</p>	<p>IAW Paint scheme -General 12 and Annex B refer.</p> <p>To be completed in conjunction with H3.05.</p>

TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.16	<p>Vehicle Deck</p>  <p>The vehicle deck has breakdown of paint coatings throughout with active corrosion evident, particularly at the aft end either side of the vehicle ramp. The total area both sides of the vehicle ramp to have REPRESENTATION carried out, and the remainder of the vehicle deck patch repair REPRESENTATION.</p> <p>ALLOW for 250m² REPRESENTATION.</p>	<p>IAW Paint scheme -General 12 and Annex B refer.</p> <p>To be completed in conjunction with H2.01, H2.02, H2.09, H2.10, H2.18, H3.01 and 3.02.</p>

TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.17	<p>Office and Toilet Block Securing Points</p>  <p>Current Office and toilet block support legs are not securely fixed to deck (welds suffering active corrosion). Following removal of existing facilities, hold-down points to be welded to deck to facilitate securing of new office and toilet block facilities. Total deck area beneath existing fit to be assessed and REPRESENTED accordingly.</p> <p>ALLOW for 8 in number securing points. ALLOW for 80m² REPRESENTATION.</p>	<p>Hotwork Required – Appropriate precautions to be taken iaw General 8.4.</p> <p>IAW Paint scheme -General 12 and Annex B refer.</p> <p>To be completed in conjunction with H2.17 and H9.02.</p>

TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.18	<p>Crane Deck and Soft Patch</p>  <p>The Crane Deck and associated removable soft patch have large areas of total paint coating breakdown and consequently are showing signs of active corrosion. Soft patch eyeplates to be removed and soft patch welded in place. On completion of crane removal (M1.01) deck and soft patch to be REPRESENTED.</p> <p>ALLOW for 25m² REPRESENTATION.</p>	<p>Hotwork Required – Appropriate precautions to be taken iaw General 8.4.</p> <p>IAW Paint scheme -General 12 and Annex B refer.</p> <p>To be carried out post M1.01</p>

TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.19	<p>Redundant Upperdeck Items</p>  <p>Numerous upperdeck fixtures and fittings are now redundant, and showing signs of paint coating breakdown and excessive corrosion. These items are to be removed and disposed of by the Contractor, and deck /bulkhead areas affected REPRESENTED on completion. Items to be removed will be identified on board by Authority's Authorised Representative.</p> <p>ALLOW for 80 man hours. ALLOW for 50m² REPRESENTATION.</p>	<p>Hotwork Required – Appropriate precautions to be taken iaw General 8.4.</p> <p>IAW Paint scheme -General 12 and Annex B refer.</p>

TASK NO.	TASK/DESCRIPTION	NOTES
	H2 HULL AND STRUCTURE – EXTERNAL DECKS AND ASSOCIATED FITTINGS	
H2.20	<p>Stern Landing Platform</p>  <p>The stern landing platform has proved to be too short to allow access for the boats offloading personnel and equipment and requires extending. New design to be agreed with Authority's Authorised Representative. PRESERVE platform on completion. Platform will be removed prior to berthing for period of Refit, work to be conducted in shoreside facility.</p> <p>ALLOW for 20m² PRESERVATION. ALLOW for 8m² extension</p>	<p>Hotwork Required – Appropriate precautions to be taken iaw General 8.4.</p> <p>IAW Paint scheme -General 12 and Annex B refer.</p> <p>To be completed in conjunction with H1.02.</p>