

TENDER CLARIFICATIONS 19TH JUNE 2020

1. Please provide details of quality submission for scoring.
 - a. Please see uploaded scoring methodology for boiler relocation document uploaded 19/06/20.
 - b. Document outlines scoring methodology for tender returns.
 - c. As per the invitation to tender, please ensure that compliant bids are returned. To be compliant tenders must include the following:
 - i. Form of Tender duly signed
 - ii. Tender Sum Analysis (Pricing Document) fully priced.
 - iii. A detailed programme for the works with critical path and associated information required.
 - iv. Outline method statement with particular regards to Delivery and Waste routes as well as site set up generally.
 - v. Evidence of your insurances, VAT registration and UTR - Three references of recent relevant works.
 - vi. Details of your company history and profile, including financial information and environmental policy

2. Q: Spec calls for the external gas pipework to be in Galv Steel with welded joints and painted. We would not normally use Galv steel on gas and would only use screwed joints. Painting galvanised is also problematic as we would also have to use a acid primer to key onto the galvanise. Please can you confirm your requirement?
 - a. Alternatives for the gas pipework are fine. Please highlight your changes in the tender return documents.

3. Q: The Spec calls for the pre-insulated pipework to have additional insulation – Please can you provide detail of what you require (type/finish/thickness)
 - a. Please contact Rehau directly.

4. Q: We also note the use of Denso tape above ground – our only concern is in hot weather the denso becomes very sticky and could be a problem if the general public have access to this area.
 - a. Denso tape may have been stated in error, what is required is a wrap to the exposed pre-insulated pipework that protects against UV e.g. venturclad.

5. Q: We note one number strainer on your schematic but we are assuming you will require strainers before each pump set as well.

- a. Yes, please allow for strainers before each pump set as well.

Tim Hopkins

Head of Estates

16.06.20