

NCC requests quotation for the following works (Ref code)

CRM ref	CMF 33: Heath Lane Access Improvement, Marriott's Way
Source	Inspection
Outcome required / Description of works	400 metres of improved surface on the Marriott's Way. Surface scrape of existing material, installation of adequate drainage to manage peak flow events. Removal of bollards, granite sub-base topped off by granite dust and mechanically tamped down to provide an improved walked, cycled and ridden surface
Completing works will result in	Access for all, improved access during winter months
Waste	surface materials from surface scrape - to create a habitat pile
Location	TG 09745 19137
Location Map	Included in quote documents
Contractor accesses / other detail in order for quote	400 metres of improved walking / cycling and riding surface. Granite sub-base blinded off with granite dust and mechanically tamped down.
CAD Drawings	Included in quote documents if required
Timetable	Deadline for delivery of improvements: By end of October 2021
Contractor quote	Subcontracting clause
Quote evaluation)	60 % Cost - 20 % Experience of Delivery of similar projects - 20 % delivery within desired timeframe
Deadline for submission	17:00 on 30 July 2021 (will be reviewed on 2 August 2021)

Disclaimer – contractor must have relevant licence/tickets to carry out works – a, b- c / must provide relevant risk assessments/ method statements for works on request or add as tick boxes?