

Remove silk covering to existing flush concealed timber doors, architraves and integrated section of skirting to be prepared as NBS M60/440, M60/460 and decorated as M60/150A. Existing ironmongery to be protected and overhauled as M60/424 and M60/430.

Refer to structural engineer specification for stitch repair along vertical crack in wall.

Scope of work to Gallery Room 01 & 02 (Room 1.18, 1.19 & 1.20)

Drawings to be read in conjunction with NBS Specification.

Ceilings:

Refer to drawing 1222 for scope of work to the ceilings.

Voids above:

Refer to drawing 1221 for scope of work to the voids above the existing ceiling level.

Walls:

Existing silk wall covering to be carefully removed and carted offsite. Apply plasterboard and skim finish to existing tongue and groove board and decorate. Refer to Detail 1 on DIA drawing 3400 for details and specification.

Metal picture rail located beneath the decorative plasterwork to be carefully removed and reinstated onto the new surface of the walls. Prepare and decorate picture railing, colour to match walls.

Doors

Ornamental painted timber doors and architraves to be prepared as NBS M60/440, M60/460 and decorated as M60/150A. Existing ironmongery to be protected and overhauled as M60/425 and M60/430.

All flush doors and frames (8.no in total) to be made good and decorated as M60/150A to match wall colour. Existing ironmongery to be protected and overhauled as M60/425 and M60/430.

Skirting

Repair, prepare and redecorate as shown on Detail 1 on DIA drawing 3400.

Floors

Existing narrow gauge strip timber floor and joists to be repaired, prepared and sealed as shown on Detail 1 on DIA drawing 3400.

1 - Gallery 01 & 02 - First Floor Plan as Existing
Scale 1:50 @ A1

N

0 0.5 1 2.5
Scale 1:50 m

Notes

1. Any dwg format drawing is to be read in conjunction with and at the scale of the accompanying pdf.
2. Where colours other than black or grey are used, the drawing must be plotted in colour.
3. For status 'C' (Construction) drawings all dimensions are to be checked on site by the contractor, scaling is for Local Authority purposes only.
4. Unless otherwise indicated, all dimensions are in millimeters.
5. All information on this drawing is to be read in conjunction with the relevant Donald Insall Associates specification and trade contractors' drawings and information by specialists.
6. In the event of any discrepancy, please contact us immediately.
7. This drawing may contain survey information by others and is to be used solely for the purposes for which it was issued.
8. These are uncontrolled documents issued for information purposes only. If you have any queries regarding the drawings, please contact DIA immediately.
9. Please note DIA cannot be held responsible for any errors arising from changes made to an uncontrolled dwg file.

© 2017 DONALD INSALL ASSOCIATES LTD

Drawing Status

- **F** Feasibility
- **S** Sketch Design
- **P** Planning
- **B** Building Control
- **D** Developed Design
- **M** Measurement
- **T** Tender
- **C** Construction
- **R** Record

Rev	Date	Dwn	Auth	Revision
5	23/10/20	HXD	EJ	Annotation updated. QS observations.
4	04/09/20	HXD	EJ	Annotation updated. Cross referencing to drawing 3400.
3	24-06-20	HXD	EJ	Amended to survey information
2	03-06-20	HXD	EJ	Annotation Updated
1	22-04-20	HXD	EJ	Lineweights amended
0	09-04-20	EJ	EJ	Initial Issue

Donald Insall Associates
Chartered Architects and Historic Building Consultants

Y Becws, Pool Lane
Conwy LL32 8PZ
(+44) 01492 592 378
conwy@insall-architects.co.uk

Walker Art Gallery, Liverpool

Gallery Room 01 & 02
Floor Plan As Existing

Project	No
WAGL.01	1220

Scale (A1)	Status	Revision
1:50	3C	5