



DS5 Existing double doors retained and locked shut. Stud wall with plaster sheathing to internal face.

New partition and 60 min fire door to create plant room. Allow for drilling through floor and fire stopping of services to link services to plant room above.

DS8 blocked with new partition to match adjacent.

New lift shaft and access bridges as drawings 976•330+

New kitchenette as drawing 976•370

New handrail installed to outer wall of main stair as drawing 976•383.

To all Second Floor structure:
Remove all spray applied concrete to all steel columns, beams and ceiling underside to reveal original structure. Make good ceiling / beam plasterwork junction.
Apply intumescent paint to all exposed steelwork. Repair floor cracks as structural engineer's details. Redecorate underside of concrete ceiling.

S7 Male WC as drawing 976•352

S8 Plant room as drawing 976•351

S9 WC as drawing 976•353

Infill former window with news studwall as drawing 976•348.

Board up windows as per window schedule

New mobile storage/ racking to be installed by client.

Form new partition to continue line of existing store at north end. Allow for new door flush door in new partition, with vision panel.

Existing exhibition machinery (Indicative dotted lines show outlines) will remain in situ already fully boxed in. Do not disturb.

Note: Spinning Jenny to remain in situ for duration of works to comply with the Science Museum's requirements.

Disabled refuge and call points installed in Stair 1 and Stair 2.

Upgrade existing stair balustrade to comply with building regulations as drawing 976•381

Make good plaster finish to blockwork wall within museum where existing boarding removed.

GENERAL NOTES

- Indicative layout of museum display (low level)
- Indicative layout of museum display (tall elements)

Windows as drawings 976•400 - 419.

Doors as drawings 976•420+

Fire strategy as drawings 976•500+

Refer to Room Data Sheets for individual room details.

Rainwater Goods as per Rainwater Schedule.

Decorations as Finishes Schedules.

Rev B: 22.10.2018
Accessible WC works reduced.
Notes updated.
Rev A: 18.09.2018
Progress Meeting
Notes updated.

DRAFT FOLLOWING CLIENT MEETING 29.6.2018

976•302B
Trowbridge Museum Redevelopment
The Shires, Court Street, Trowbridge
Wilts. BA14 8AT
for Trowbridge Town Council
FIRST FLOOR PLAN
PROPOSED
1:100 @ A1 June 2018
ARCHITECTON
The Wool Hall 12 St Thomas Street
Bristol BS1 6JJ
t 0117 9105200 f 0117 9260221
e info@architecton.co.uk