



CROWTHORNE PARISH COUNCIL ('the Council') INVITES TENDERS FROM INTERESTED CONTRACTORS ('The Contractor')
FOR
PLAY AREA SAFETY SURFACE RESURFACING AND CLEANING AT THE MORGAN RECREATION GROUND, LOWER
BROADMOOR ROAD, CROWTHORNE RG45 7LA ('The Morgan Recreation Ground')

Tender deadline:

All tenders to be submitted electronically to clerk@crowthornepc.org.uk by mid-day on Friday 4 June 2021.

Delivery schedule:

It is anticipated works will take place before the school summer holidays in 2021 in order to avoid adversely impacting use of play equipment during the holidays. Contractors should indicate in their tender that they will be able to complete the works before Thursday 15 July 2021 if awarded the contract.

Before Commencement of Works:

- (1) Contractor to provide to the Council written reference from 2 public sector works contracts and contact details for their referee for similar play area safety surface resurfacing works carried out by the contractor in the last 3 years verifying works completed on budget, on time and to a standard which was satisfactory to the buyer.
- (2) Contractor to provide written risk assessments, method statements, evidence of public liability insurance and other industry specific paperwork which is acceptable to the Council.
- (3) Visits to site can be arranged by phoning the Clerk on 07788 372444 although the site is open to the public at all times so can be accessed without an appointment.

The Works:

Address: The Morgan Centre, Wellington Road, Crowthorne,
RG45 7LD Access: Car Park next to play area

You are invited to tender by quote for the works below.

All surfaces must comply with BSEN1177 and BS7188 and have a minimum of 5 years' warranty.

Gym Area: 43m²

- Supply and install approx. 20m² of type 1 stone in-between fitness equipment.
- Supply and install weed suppressing membrane
- Supply and install 43m² Tiger mulch in Autumn blend rolled into the ground at a depth of 40mm

Subtotal:

VAT:

Total:

Teen Shelter: 26m²

- Supply and install 26m² of Tiger Mulch over-skim with a green EPDM wear pad half round
- Area to include bin and all rolled into the ground at 40mm depth.

Subtotal:

VAT:

Total:

Basket Swing: 28m²

- Supply and install 28m² of Tiger Mulch to a depth of 40mm rolled into the ground.
- Supply and install Colour EPDM wear pad in Green to match the fitness equipment and bike rack.

Subtotal:

VAT:

Total:

Rope end swing including trampoline and joining basket swing: 148m²

- Supply and install 148m² of Tiger Mulch to a depth of 40mm rolled into the ground.
- Supply and install Colour EPDM wear pad Arrows under the rope swing in Green to match the fitness equipment and bike rack.
- Dig out and chase cut around edge of trampoline for ease of future maintenance

Subtotal:

VAT:

Total:

Slide area: 34m²

- Supply and install 34m² of Tiger Mulch to a depth of 60mm due to the free fall height requirement, rolled into the ground.
- Supply and install Colour EPDM wear pad splash at the bottom of the slide and patch at the bottom of tower.

Subtotal:

VAT:

Total:

Rock Climbing area: 43m²

- Supply and install 43m² of Tiger Mulch to a depth of 60mm due to the free fall height requirement, rolled into the ground. Including small 5m² path to rock that is on the steepest part of the slope that is extremely slippery.

Subtotal:

VAT:

Total:

Toddler play area and bike park

Scrub of all surfacing and equipment in the toddler area and bike park, including:

- Preparation of all Equipment and surfacing for Tiger Scrub – removal of fallen vegetation/detritus
- Power wash approx. 350m² surfacing
- Application of anti-fungal inhibitor to deter grime and algae/moss regrowth

Supply and install 3m² of patch repairs in black EPDM (toddler area) where surfacing has corroded

Subtotal:

VAT:

Total:

Subtotal for all**VAT:****Total:**