

Engineering and Construction Short Contract

Contract Data Forms

June 2017 (with amendments January 2023)

Template version history

V1 (as per bidder pack)	Go live template (this document)

NEC4 Engineering and Construction Short Contract

A contract between	The Environment Agency
	Horizon House
	Deanery Road
	Bristol
	BS1 5AH
	,
And	Land & Water Services Ltd
For	Golden Valley Weir Improvement Project
	Contract Forms - Contract Data - The Contractor's Offer and Client's Acceptance - Price List - Scope - Site Information

Contract Data

The <i>Client's</i> Cor	ntract Data		
	The Client is		
Name	Environment Agency		
Address for communications	Rivers House, East Quay, Bridge	water, Somerset, TA6 4YS	
Address for electronic communications			
The works are	Repair to the Golden Valley Wei stone eel pass	r and the installation of embedded	
The site is	Golden Valley Weir, Golden Valley Lane, Bitton, South Gloucestershire, BS30 6NZ (NGR ST 68347 69976)		
The starting date is	26/02/2025		
The completion date is	01/10/2025 _31/03/2026		
The delay damages are	£99	Per day	
The <i>period</i> for reply is	2	weeks	
The defects date is	52	weeks after Completion	
The defects correction period is	4	weeks	
The assessment day is	the last working day	of each month	
The retention is	nil	%	

The United Kingdom Housing Grants, Cons	truction and Rec	generation Act (1996) does	s apply
The Adjudicator is:			
In the event that a first dispute is referred Institution of Civil Engineers to appoint an Adjudicator of the Adjudicator. The referring person appointed is also Adjudicator for late	A <i>djudicator</i> . The Party pays the	application to the Institution	on includes a copy of this
Contract Data			
The <i>Client's</i> Con	tract D	Data	
The interest rate on late payment is		% per complete week	of delay.
Insert a rate only if a rate less than 0.5%	per week of de	lay has been agreed.	
For any one event, the liability of the Contractor to the Client for loss of or damage to the Client's property is limited to	The Contract F	Price	
The <i>Client</i> provides this insurance	None		
	Insurance 1	Table	
Event		Cover	Cover provided until
Loss of or damage to the works		Replacement Cost	The Client's certificate of Completion has been issued
Loss of or damage to Equipment, Plant and	Materials	Replacement Cost	The defects Certificate
The Contractor's liability for loss of or dama (except the works, Plant and Materials and and for bodily injury to or death of a per-	nd Equipment)	Minimum £5,000,000 in respect of every claim without limit to the	has been issued

number of claims

	yee of the Contractor) arising from one Contractor's Providing the Works	r in connection		
Contra	ry for death of or bodily injury to empactor arising out of and in the conyment in connection with this contract	ourse of their	The amount required by the applicable law	
	Failure of the <i>Contractor</i> to use the skill and care normally used by professionals providing works similar to the works		Minimum Contract Price in respect of every claim without limit to the number of claims	6 years following Completion of the whole of the works or earlier termination
The A	dividiantor nominating hady in	The Institution	of Civil Engineers	
THE A	djudicator nominating body is	The institution	of Civil Engineers	
The tri	ibunal is	litigation in the	e courts	
		1		
	onditions of contract are the NEC4 Enamendments) and the following addition		Construction Short Contrac	t June 2017 (including
Only e	enter details here if additional cond	litions are requ	ıired.	
Z1.0	Sub-contracting			
Z1.1	The Contractor submits the name of for not accepting the subcontractor Works. The Contractor does not ap	is that their app	pointment will not allow the	Contractor to Provide the
Z1.2	Payment to subcontractors and sup	opliers will be no	more than 30 days from re	eceipt of correct invoice.
Z2.0	Environment Agency as a regulator	ry authority		
Z2.1	The Environment Agency's position and distinct. Actions taken in one care			
Z2.2	Where statutory consents must be authority, the <i>Contractor</i> is respons the Scope). The <i>Client's</i> acceptandoes not constitute statutory approximately.	sible for obtainir ce of a tender	ng these and paying fees (unless stated otherwise in
Z2.3	An action by the Environment Ager compensation event.	ncy as regulator	y authority is not in its capa	acity as <i>Client</i> and is not a
Z3.0	Confidentiality & Publicity			
Z3.1	The Contractor may publicise the works only with the Client's written agreement.			
Z4.0	Correctness of Site Information			
Z4.1	Site Information about the ground, by the <i>Client</i> but is not warranted Information they rely on for the purp	I correct. The (Contractor checks the corr	
Z5.0	The Contracts (Rights of Third Part	ies) Act 1999		
Z5.1	For the purposes of the Contracts (purports to confer on a third party a			
Z6.0	Design			
Z6.1	Where design is undertaken, it is normally used by professionals pro			the use of skill and care
Z6.2	The Contractor designs the parts of the works which the Scope states they are to design.			
	•			

Z6.3	The <i>Contractor</i> submits the particulars of their design as the Scope requires to the <i>Client</i> for acceptance. A reason for not accepting the <i>Contractor</i> 's design is that it does not comply with either the Scope or the applicable law.
	The Contractor does not proceed with the relevant work until the Client has accepted this design.
Z6.4	The Contractor may submit their design for acceptance in parts if the design of each part can be assessed fully.
Z7.0	Change to Compensation Events
Z7.1	Delete the text of Clause 60.1(11) and replace by:
	The works are affected by any one of the following events
	War, civil war, rebellion revolution, insurrection, military or usurped power
	• Strikes, riots and civil commotion not confined to the employees of the <i>Contractor</i> and sub-contractors
	Ionising radiation or radioactive contamination from nuclear fuel or nuclear waste resulting from the combustion of nuclear fuel
	Radioactive, toxic, explosive or other hazardous properties of an explosive nuclear device
	Natural disaster
	Fire and explosion
	Impact by aircraft or other device or thing dropped from them
Z8.0	Framework Agreement
Z8.1	The Contractor shall ensure at all times during this contract it complies with all the obligations and conditions of the Framework Agreement made with the Client.
Z9.0	Termination
Z9.1	Delete the text of Clause 92.3 and replace with:
	If the <i>Contractor</i> terminates for Reason 1 or 6, the amount due on termination also includes 5% of any excess of a forecast of the amount due at Completion had there been no termination over the amount due on termination assessed as for normal payments.
Z10.0	Data Protection
Z10.1	The requirements of the Data Protection Schedule shall be incorporated into this contract
Z11.0	Liabilities and Insurance
Z11.1	Civil data protection claims and regulatory fines for breaches of Data Protection Legislation are excluded from any limit of liability stated.
Z110	Inflation
	At the Contract Date the total of the Prices does not include a sum to cover inflation.
	The total of the Prices [at the Contract Date] shall be adjusted by a fixed number of Price Adjustments.
	The number of Price Adjustments shall be equal to:
	The number of months between the Completion Date included at the starting date and the Contract Date.
	The proportion of Price Adjustment shall be equal to:
	The total of the Prices at the Contract Date / The number of Price Adjustments

The proportion of Price Adjustment x [80% x Construction Output Price Indices (OPIs) New work output prices: Infrastructure Index 1 – month rate]

The Construction Output Price Indices (OPIs) New work output prices: Infrastructure Index 1 – month rate shall be the value determined by the Office of National Statistics for the applicable month of the amount due assessment

Provided always that the fixed number of Price Adjustments has NOT been exceeded.

The Price Adjustment adjusts the total of the Prices.

If a compensation event under this contract omits original Scope covered by the total of the Prices at the Contract Date the Price Adjustments made under this clause shall be corrected accordingly.

Contract Data

The Contractor's Contract Data				
		Data		
	The Contractor is			
Name	Land & Water Services Ltd			
Address for communications	Albury Mill, Mill Lane, Chilworth, C	Guildford, GU4 8RU		
Address for alcotonic				
Address for electronic communications				
TI. (_	Lov		
The fee percentage is		%		
The people rates are				
category of person	unit	rate		
The published list of Equipment is				
The percentage for adjustment for I	Equipment is			
		I .		

Contract Data

The *Contractor's* Offer and *Client's* Acceptance

The Contractor offers to Provide the determined in accordance with thes	e Works in accordance with these <i>conditions of contract</i> for an amount to be se <i>conditions of contract</i> .
The offered total of the Prices is	£299,290.43
	Enter the total of the Prices from the Price List.
Signed on behalf of the Contractor	
Name	
Position	
Signature	_*
Date	28/01/2025
The Client accepts the Contractor's	Offer to Provide the Works
Signed on behalf of the Client	
Name	
Position	
Signature	

Date	24/02/2025

Price List

Entries in the first four columns in this Price List are made either by the Client or the tenderer.

If the *Contractor* is to be paid an amount for the item which is not adjusted if the quantity of work in the item changes, the tenderer enters the amount in the Price Column only: the Unit, Quantity and rate columns being left blank.

If the *Contractor* is to be paid an amount for the item of work which is the rate for the work multiplied by the quantity completed, the tenderer enters the rate which is then multiplied by the expected quantity to produce the Price, which is also entered.

Item Number			Quantity	Rate	Price	
1	Obtain required permits/ consents for permanent and temporary works	Ea	1			
2	Site start up meeting to confirm scope and site constraints	Ea	1			
4	Mobilisation - Site setup, supervision, running costs	Ea	1			
4a	Mobilisation - Site setup	Ea	1			
4b	Supervision, running costs		1			
4c	Demobilisation		1			
5	CDM documentation and sign off (including PCI, CPP, RAMS and H&S File input)		1			
6	Design, installation and removal of Temporary Works	Ea	1			
7	Refurbishment of weir (including installation of eel pass, access steps and fencing)		1			
7a	Removal of redundant steel beams		1			
8	Provision of 'as constructed' carbon calculations and 'as constructed drawings	Ea	1			

The method and rules used to compile the Price List are

The total of the Prices

£299,290.43

Civil Engineering Standard Method of Measurement 4th edition (CESMM4) as per the Framework Price Workbook.

Scope

1. Description of the works

Overview

Golden Valley Weir (the Site) is a 4 x step concrete capped gabion weir structure located on the River Boyd, on the northern outskirts of the village of Bitton (see Site Location and Boundary Plan in the Site Information – **Appendix A**). The weir is approximately 13m long x 14m wide, with each step approximately 1m in height. The weir was originally installed as a two-step weir on the River Boyd in the 1970s as part of the Bitton Flood Alleviation Scheme (FAS). In 2003 it was reconstructed into a four-step gabion weir to expand the weir as well as fixing damage to the original lower gabion step. Further details including construction photos can be found within the Bitton FAS Operation and Maintenance Manual (Site Information – **Appendix B**).

The weir is now failing with a fallen gabion wall section at the downstream end (see photos below), and washout areas around the upstream left bank wingwall creating voids behind the weir gabion walls and causing leaks through the walls within the structure itself. If left unrepaired, the erosion to the bank behind the structure will eventually cause the weir fail completely with further wall collapses as observed on the left bank immediately downstream of the structure (see photos below).





It is understood that there were also leaks on the right bank, which have been temporarily stemmed and were not visible during the outline design stage.

Golden Valley Weir also presents a significant obstruction to eel passage, limiting the extent of available eel habitat upstream of the award-winning eel pass at the Ski Jump structure approximately 250m downstream.

The *Client* has a legal obligation under the Eels (England and Wales) Regulations 2009, to provide safe passage of eels past this obstruction.

Objective

The primary objective of this work is to repair the Golden Valley Weir and install an embedded stone eel pass. This will reinstate the weir back to its required standard of protection, reduce flood risk as part of the Bitton FAS,

retain the upstream water levels for angling and abstractions, improve the life span of the asset and provide an eel passage solution that is safe to operate and maintain.

Scope - Detailed Design Phase

To deliver the above *Client* objectives and the following scope, the *Contractor* will assume the role of Principal Contractor.

Pre Construction Stage

Prior to works commencing on site the *Contractor* shall:

- Undertake a photographic pre-construction condition survey of the structure, access routes, and proposed
 compound/working areas that will be affected by the works. The pre-construction photographic condition
 survey is to be presented in a concise standalone survey report, with key locations and any existing
 defects clearly identified and referenced. The report is to be provided to the Client one week before any
 works start on site;
- Apply for and manage, using all reasonable endeavours, any required Right of Way diversion/closure and Flood Risk Assessment Permit(s) (FRAP);
- Before any work commences on site, undertake an ecological walkover to reaffirm the findings of the
 Preliminary Ecological Appraisal (PEA) undertaken during the design phase. Findings are to inform the
 Contractor's ecological toolbox talk to their staff, which will include any mitigation for protected species,
 biosecurity requirements for non-native or invasive species, and measures to prevent debris or pollutants
 entering the watercourse. The Client's project team are to be invited to the toolbox talk; and
- Provide their proposed approach for site access, welfare and storage provisions via a simple annotated plan.

Before construction can commence the *Contractor* shall liaise with the *Client's* project team and Residential Principal Designer to develop and gain *Client* approval of:

• Pre-Construction Information (PCI), Construction Phase Plan (CPP), Traffic Management Plan, Risk Assessments and Method Statements (RAMS).

Temporary works design, RAMS and calculations must also be provided to the Principal Designer for acceptance.

Construction Stage

To deliver the works the *Contractor* shall, as per the *Client* approved designs and the Principal Designer accepted approved CPP and RAMS:

- Mobilise to site and set up the site compound, storage areas and safety signage as required;
- Install any *Client* accepted Temporary Works design and, once installed, obtain sign off from the *Contractor's* appointed Temporary Works Supervisor;
- Implement Client accepted designs (including removal of the derelict bridge remains);
- Reinstate the working areas and any disturbed access routes, reseeding green areas where required; and.
- Demobilise.

Post Construction Works

The *Contractor* shall liaise with the *Client's* project team, Designer and CDM Principal Designer (See **Appendix 2** of PCI for contact details), to provide:

• Marked up 'as constructed' drawings, identifying any deviations from the design accordingly. Any deviations from the *Client* accepted design are to be clearly communicated to the Designer to enable the

- Designer to issue final 'As constructed' drawings in both .pdf and .dwg format ready for submission to the Principal Designer for approval;
- Contractor CDM Health and Safety File input/information to enable the Principal Designer to finalise the CDM Health and Safety File (initial draft provided);
- a photographic post-construction condition survey of any access routes to the structure, and areas around
 the structure that will be affected by the works, especially any compound area and working areas. The
 post-construction photographic condition survey is to be presented in a concise standalone photographic
 report, with key locations and any existing defects clearly identified and referenced. The report is to be
 provided to the Client one week after demobilisation from the site and will be required before 'Completion'
 is certified; and,
- A separate electronic folder containing copies of the photographs of the works pre-, during and post-construction.

2. Drawings

Drawing Number	Revision	Title
A120100-TGEE-GV-22-DR- C-0010	C01	Site Hazard Plan
A120100-TGEE-GV-22-DR- C-0017	C01	Proposed Eel Pass Details
A120100-TGEE-GV-22-DR- C-0018	C01	Fencing Details
A120100-TGEE-GV-22-DR- C-0019	C01	Proposed Eel Pass Design
A120100-TGEE-GV-22-DR- C-0020	C01	Section and Details

3. Specifications

Title	Date or Revision	Tick if publicly available
Environment Agency Blockage Management Guide (Gov.uk)	12/2019	yes
Latest Ciria Guidance: Culvert, screen and outfall manual - New CIRIA guidance	12/2019	yes
Elver and Eel Passes: A guide to the design and implementation of upstream and downstream passage solutions at weirs, tidal gates and sluices LIT55165	12/22	yes
Safety, Health, Environment and Wellbeing (SHEW) Code of Practice (CoP)	09/23	

Doc No 249_18_SD15

4. Constraints on how the Contractor Provides the Works

The access date for the site is week commencing 26/02/2025.

The *Contractor* shall not commence any work on the site until the *Client*, or their representative, has accepted the method statements and risk assessments related to this contract.

No work can be undertaken on site until all relevant permissions and consents have been obtained.

The *Contractor* shall provide minimum 3 weeks notice before starting any works on site so the *Client's* Estates team can contact landowners and carry out landowner access negotiations.

The design of any Temporary Works and access must take into consideration the potential presence of protected and non-native species.

NOTE – Signal crayfish and Himalayan balsam have been observed in close proximity to the weir structure.

Working times

The Contractor will be permitted to work between 7.30am and 6.00pm on weekdays (Monday to Friday).

5. Requirements for the programme

The *Contractor* shall submit his programme with the *Contractor's* Offer for acceptance. The *Contractor* shall show on each programme which they submit for acceptance (in the form of a Gantt chart showing the critical path, proposed order and timing to undertake the works and proposed plant and labour resources) the following:

- (a) Period required for mobilisation/ planning & post contract award
- (b) starting date
- (c) Each of the activities listed within the Price List
- (d) Any key third party interfaces: lead in periods for materials and sub-contractors; time required to obtain consents/waste permits; stated constraints; *Contractor's* risks
- (e) Completion date

Delivery Timeframe and Programme

For programming purposes the *Contractor* must allow a minimum of 10 days for any *Client* /Principal Designer review.

The programme is to include the date required for land access notices and is to be issued a minimum of 2 weeks prior to mobilisation.

The construction work is to be completed during the summer months within the 2025/26 Financial Year.

6. Services and other things provided by the Client

Item	Date by which it will be provided
Services Search Returns Note - the above services information does not remove the <i>Contractor</i> or Contractor's requirement to carry out safe working practices in relation to overhead and underground services.	Included. Returns will be updated 2 weeks prior to CPP submission.
A120100-TGEE-WE-02-RP-C-0801 P03_Golden Valley Weir Options Report	Included in Site Information
Preliminary environmental screening and appraisal from NEAS and/or local FBG team.	Contract Award
Topographical Survey, Ground Investigation Factual Report and GPR findings.	Included in Site Information

Site Information

See provided 'Site Information' document and associated zip file that includes

- PCI Document
- Services search returns, including GPR undertaken at design stage
- Golden Valley Weir Location Plan
- A120100-TGEE-WE-02-RP-C-0801 P03_Golden Valley Weir Options Report
- Bitton FAS Operation and Maintenance Manual
- GI Factual Report
- Topographical Survey
- Bridge Inspection Report

Golden Valley Weir drawings provided for general information purposes;

- 2589-00-001 Original Weir General Arrangement
- 2589-00-002 Modified Weir General Arrangement

Proposed sub-contractors			
	Name and address of proposed subcontractor	Nature and extent of work	

Proposed sub-contractors				
1.				
	Form of Contract:			
2.				
	Form of Contract:			
3.				
	Form of Contract:			
4.				
	Form of Contract:			