

**National Asset Delivery
Technical Surveys and Testing**

**Site Information for
A43/M40 Ardley Drainage Survey
(To Outfall)**

1 SITE INFORMATION

- 1.1. The principal objective of the works is to undertake a full asset inventory and condition survey of the drainage network along the M40 from the Ardley roundabout Northbound entry slip road.
- 1.2. A survey was carried out at Ardley roundabout a few years ago. It has been highlighted that the drainage run is required to be surveyed to outfall to determine its condition. As-built drawings show the outfall to be on the SB M40 at MP106/4+50.

2 SITE BOUNDARY, EXTENTS AND ACCESS ARRANGEMENTS

- 2.1. The Contractor's working hours for site works shall be night time, between 20.00 – 06.00
- 2.2. Works along the M40 will be under the protection of lane closures. A TTRO will be in place to survey the drainage along the slip road.

3 DRAINAGE

- 3.1. The survey extents are along a 400mtr section of the M40 motorway (MP106/1 - MP106/5).
During a past survey, it was discovered that the drainage network was surcharged. Therefore, this will require de-watering prior to surveying.

Note: The outfall must be located and surveyed.

See Schedule of Requirements for full specification.