



Trewen Bridge Weir Fish Passage Improvement - 22 July 2019

Further to the issue of the ITT request, we would like to provide some additional information relating to the project.

1. The proposed layout has been adjusted, please refer to the attached Proposed Layout Plan and Sections – Existing and Proposed, both revision B.

The adjustments comprise – a narrower eel pass, the low flow notch through the baffles has been handed, a pre-barrage baffle is included at the proposed weir toe and the eel tiles have been removed from beneath the bridge.
2. The construction of the proposed fish easement requires a high degree of construction accuracy. As such, the appointed contractor will be required to install temporary benchmarks to ensure all levels can be accurately crosschecked to Ordnance Survey datum as provided on the topographical survey for the site.
3. All in-river works need to be completed by 30 September 2019. Should this not be possible, the intention is to complete the works next year at the earliest opportunity, prior to 30 September 2020.
4. All pumps must be suitably screened to ensure against the ingress of fish.
5. WRT will be on standby during dewatering to rescue stranded fish as required.