



FIRST FLOOR PLAN PROPOSALS

Internal Partitions
 Install 95mm o/a internal partitions comprising of 70 Gyproc® "C" studs @ 600mm centres to manufacturers recommendations and details lined both sides with 12.5 mm Gyproc wallboard and plaster skim finish.
 Provide acoustic mineral wool insulation between studs (APR 1200)
 Partitions built up and fixed to existing roof trusses and fire stopped.
 * Doors re-located from ground floor Phase 1.

Rev.	Description	By	Date
------	-------------	----	------

Client
Maritime Coastguard Agency

Project
**Crosskill House
 Beverley**

Drawing Title
**Proposed Layout Plan
 First Floor**

Drawing No. **LEBS0806/FF/03**

Scale **1:100 @ A1** Original Sheet Size A1

Drawing Status	
Drawn CD	Checked
Date 01/17	Rev.



International
 Management &
 Construction Consultants