

MBA CONSULTING

MultireBAR Schedule ref:

24060/53

01

Rev.
A

Site ref: PENZANCE DRY DOCK
WHARF ROAD,
PENZANCE.

Date prepared: OCT.'24

Date revised:

Location: R.C. DETAILS ON WORKSHOP SLAB.

Prepared By: DAF

Checked by: GM

Job No: 24060

Member	Bar mark	Type & size	No of mbrs	No of bars in each	Total no	Length of each bar † mm	Shape code	A mm *	B mm *	C mm *	D mm *	E/R mm *
R.C. Details on	01	H 12	1	638	638	1200	21	500	225	(500)		
Workshop Slab.	02	H 12	1	4098	4098	6000	00	(6000)				
	03	H 12	1	210	210	3500	00	(3500)				
	04	H 12	1	224	224	3000	00	(3000)				
	05	H 12	1	561	561	1175	21	500	200	(500)		
	06	H 20	1	46	46	2700	00	(2700)				
	07	H 20	1	20	20	2400	00	(2400)				
	08	H 20	1	3280	3280	3000	00	(3000)				
	09	H 20	1	96	96	6000	00	(6000)				
	10	H 20	1	30	30	1825	00	(1825)				
R.C. Details on	11	H 10	1	74	74	1175	51	175	325	130	(130)	
Tie Beams.	12	H 10	1	74	74	800	51	175	140	130	(130)	
	13	H 16	1	48	48	1800	11	175	(1650)			
	14	H 16	1	8	8	3550	00	(3550)				
	15	H 16	1	72	72	1825	11	750	(1100)			
	16	H 10	1	18	18	1475	51	325	325	130	(130)	
	17	H 16	1	24	24	2050	21	900	305	(900)		
	18	H 16	1	8	8	3475	00	(3475)				
	19	H 16	1	8	8	2675	00	(2675)				
	20	H 16	1	8	8	1875	00	(1875)				
	21	H 16	1	8	8	1075	00	(1075)				