



## Schedule of Works

Item ref	Name	Units	Quantity	Unit price	Cost
Section: Tip Works - Multiple Sites V-Notch Weirs and Fencing surrounding Piezo Loggers					
ECO-D03	Temporary Welfare Facilities - 2 to 5 days	Day			
	Description: Provision of temporary welfare facilities for works of 2 to 5 days duration				
CECA+4 - 06.38	Concrete Saw, Blade dia. 350mm	Hour			
	Description: Concrete Saw (excl. of blades and water supply to be charged in addition) manually propelled Blade dia. up to 350mm				
CECA+4 - 05.01	Tilting Drum Mixer 90 Litres	Hour			
	Description: Tilting Drum Mixer Wet Capacity up to 90 Litres				
CECA+4 - 10.15	Hydraulic Full Circle Slew, 2 tonnes	Hour			
	Description: Hydraulic Full Circle Slew, Crawler or Wheel Mounted, With Single Equipment. Maker's rated nominal weight of machine up to 2.0 tonnes				
CECA+4 - 10.18	Hydraulic Full Circle Slew, 6 tonnes	Hour			
	Description: Hydraulic Full Circle Slew, Crawler or Wheel Mounted, With Single Equipment. Maker's rated nominal weight of machine up to 6.0 tonnes				
ECO-C01	Foreman - 08:00 to 16:30 M-F	Hour			
	Description: Normal Working Week Monday to Friday 08.00 to 16.30				
ECO-C05	Labourer / Drain Layer - 08:00 to 16:30 M-F	Hour			
	Description: Normal Working Week Monday to Friday 08.00 to 16.30				

Item ref	Name	Units	Quantity	Unit price	Cost
ECO-C09	Machine Driver / Operator - 08:00 to 16:30 M-F Description: Normal Working Week Monday to Friday 08.00 to 16.30	Hour			
ECO-C45	Chain Saw Operator - 08:00 to 16:30 M-F Description: Normal Working Week Monday to Friday 08.00 to 16.30	Hour			
ECO-C61	Lorry Driver - 08:00 to 16:30 M-F Description: Normal Working Week Monday to Friday 08.00 to 16.30	Hour			
14 (26)	Pick Up Truck Description: Pick Up Truck - Cwmtillery, Ty Mawr, and Ogmore Tips	Sum			
CECA+4 - 14.03	Lorry, Ordinary, 12.0 tonnes Description: Lorry, Ordinary (site use and public highway use incl. Tax, Insurance and extra cost of petrol or DERV). Plated gross vehicle weight up to 12.0 tonnes	Hour			
CECA+4 - 14.09	Lorry, Articulated, 39.0 tonnes Description: Lorry, Articulated (site use and public highway use incl. Tax, Insurance and extra cost of petrol or DERV). Plated gross vehicle weight up to 39.0 tonnes	Hour			
CECA+4 - 14.22	Van, Pick Up or Similar - 1.30 tonnes Description: Van, Pick Up or Similar Utility Vehicle . Carrying Capacity up to 1.30 tonnes	Hour			
15 (1)	Trailer Description: Trailer, at Cwmtillery Tip	Sum			
ECO-E01	Metal Palisade Fence, 2.4m high, 1-10m length Description: Provide metal palisade fence 2.4m high, main posts at 2.75m centres to be concreted, pales at 152mm centres with defender heads. Concrete blocks around middle three pales up to bottom rail, galvanised finish as Steelway Fensecure Korapal SP or similar approved. All bolted connections to be Huck bolted and angled welded after erection all as per Drawing SD 001, to the following length : 1 - 10m	Metre			

Item ref	Name	Units	Quantity	Unit price	Cost
ECO-E13	Metal Palisade Gate, 2.4m high, 1m wide  Description: Provide metal palisade gate 2.4m high x 1m wide, main posts to be concreted, gate pales at 152mm centres with defender heads as Steelway Fensecure Korapal SP or similar approved	Each			
ECO-E36	Timber Post, Stock Proof, Galvanised wire Fence, 1.2m high, 11-50m length  Description: Provide 1.2 metres high timber post and stock proof galvanised wire fencing, in accordance with drawing SD 011, to the following length : 11 - 50m	Metre			
K2	Various - See Description  Description: K2 Items Aberfan - Materials Inv + 12.5% [REDACTED] Cwmtillery - Clay Inv + 12.5% [REDACTED], Materials Inv + 12.5% [REDACTED], Notch Inv + 12.5% [REDACTED] Ogmore - Grids Inv + 12.5% [REDACTED], Marine - Notch Inv + 12.5% [REDACTED]	Sum			
1	Tripod, winch etc (Inv + 12.5%)  Description: Tripod, winch etc (Inv + 12.5%) - Aberfan	Sum			
2	Highcube Unit (Inv + 12.5%)  Description: Highcube Unit - Ty Mawr Tip	Sum			
21 item(s)				Section cost: £22,622.40	
21 item(s)				Total cost: £22,622.40	