

South West Design Services Contract

Survey Specification:

Drainage / Pre-inspection condition survey of existing chamber covers

A36 Salisbury BD MP 63.1-64.4 Resurfacing

PIN 569189

Document No.: HE569189-KIER-HPV-A36_63.1_64.4_A_B-SU-CH-0000-08

April 2020



Kier Services | Highways

Brunel House
930 Hempton Court
Aztec West
Almondsbury
Bristol
BS32 4SR

Document Control

Contract Title	South West Design Services
Title	569189 A36 Salisbury BD MP 63.1-64.4 Resurfacing
Survey Discipline:	Drainage / Pre-inspection condition survey of existing chamber covers
Document No.	HE569189-KIER-HPV-A36_63.1_64.4_A_B-SU-CH-0000-08
Revision	Rev A
Status	Survey Works
Control Date	07-04-2020

Record of Issue

Issue	Rev	Organisation	Contact	Copies	Date
001	A	Highways England	██████████	1 No. (Electronic)	07-04-20

Survey Specification

Survey Brief:	<ol style="list-style-type: none">Mobilisation of survey works,Pre-survey of affected ironwork chamber covers as detailed on survey drawings HE569189-KIER-HPV-A36_63.1_64.4_A_B-SU-CD-0500-01-03 to capture the following elements at each location:<ol style="list-style-type: none">Type (Class) of chamber cover,Dimensions of chamber cover,Existing condition of chamber cover,Existing depth of brickwork / concrete above cover slab to underneath of frame,Existing condition of brickwork / concrete as detailed in item (d),To compile a report to include:<ol style="list-style-type: none">Dimensions of existing features and photographic evidence with particular attention to any defects,Proposed remedial works required to be itemised at each location. <p><u>Please note, this is a visual condition / inspection survey ONLY.</u></p> <p><u>All reinstatement works as identified during the survey works, will be undertaken during the construction phase of the scheme.</u></p>
Traffic Management:	<p>Following discussion with the HE Survey Team the anticipated Traffic Management options are as follows:</p> <ul style="list-style-type: none">TM to be night time lane closure for chambers that are located within the running lane, and total closure for any chambers located within the middle of the running lanes.Please refer to survey drawings HE569189-KIER-HPV-A36_63.1_64.4_A_B-SU-CD-0500-01-03 for locations of chambers.