



REMOVE THE EXISTING BATH AND MAKE GOOD THE WOODEN FLOOR. REMOVE THE EXISTING SINK UNIT AND REMOVE THE HOT AND COLD WATER SERVICE PIPE WORK SO THAT THERE ARE NO DEAD ENDS. MAKE GOOD WOODEN FLOOR. REMOVE FLOOR COVERING. REMOVE THE EXISTING WC AND WASH HAND BASIN.

MODIFY THE EXISTING SOIL PIPE SO THAT IT RUNS ON THE SURFACE AND EXTEND TO PICK UP THE WC. THE EXISTING UNIT IS TO BE REUSED. THE EXISTING SERVICES EXTENDED TO FEED IT. EXPOSED BASIN WASTE TO BE CHROME. COPPER PIPEWORK TO BE PAINTED WHITE. REPLACEMENT FLOOR TO BE ALTRO RELIANCE ARENA /D2510

INSTALL SMALL BUTLER AND ROSE WITH VICTORIA TAP AND STRAINER WASTE BUTLERS SINK AND UNIT. DOORS TO BE COOK AND LEWIS CARISBROOK TAUPE FRAMED ADDITIONAL BASE UNIT IS THE HOUSE INTEGRATED FRIDGE. AN A HIGH LEVEL MICRO WAY WILL BE INSTALLED WITHIN ITS OWN CABINET. WORK TOP TO BE BUTCHER BLOCK SOLID WOOD PRE-TREATED FINISH. REPLACEMENT FLOOR TO BE ALTRO RELIANCE ARENA /D2510

Rev.	Revision Notes	Date
A	- DRAFT ISSUE	_11-02-17
B	-	-
C	-	-
-	-	-
-	-	-

Rev.	Revision Notes	Date
A	-	-
B	-	-
C	-	-
-	-	-
-	-	-

TENDER ISSUE



Job Description	Date	Scale	Drawn	Checked
REPLACEMENT HEATING SYSTEM	05.02.2017	1:100		AA/AA
Location	Drawing Title			
BODMIN TOWN COUNCIL OFFICE	PROPOSED TOILET ALTERATIONS FIRST FLOOR			
Client	Dwg. No.	Rev.		
BODMIN TOWN COUNCIL	M708	A		