CHIMNEY STACK NO.1 (SOUTH SIDE)



CHIMNEY STACK NO.1 (EAST SIDE)

CHIMNEY STACK NO.1 (NORTH & WEST SIDES)



CHIMNEY STACK NO.2 (SOUTH & EAST SIDES)

CHIMNEY STACK NO.2 (NORTH & WEST SIDES)

GENERAL NOTES

1. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS, ENGINEERS AND SPECIALIST DRAWINGS AND SPECIFICATIONS
2. DO NOT SCALE FROM THIS DRAWING IN EITHER PAPER OR DIGITAL FORM. USE WRITTEN DIMENSIONS ONLY.

CONSERVATION REPAIR NOTES

1. RAKE OUT ALL CRACKED AND LOOSE POINTING TO MIN. 20mm DEPTH.

   PROVISIONALLY ALLOW TO REPOINT 75% OF BRICKWORK AREA - TO BE ADJUSTED PRO-RATA ON COMPLETION
2. ALLOW TO USE HAND TOOLS ONLY FOR MORTAR REMOVAL - DO NOT DAMAGE BRICK FACES OR ARRISES.
3. DO NOT REMOVE SOUND AND WELL BONDED CEMENTITIOUS MORTAR.
4. REPOINT USING NHL 3.5:SHARP SAND MORTAR IN 1:2.5 RATIO. SAND FOR POINTING TO BE WELL-GRADED.
5. POINTING MORTAR TO BE OF CONSISTENT COLOUR. PROVIDE SAMPLES FOR CLIENT APPROVAL PRIOR TO COMMENCEMENT.
6. JOINT PROFILE AND APPEARANCE TO MATCH EXISTING.
7. INDIVIDUAL BRICKS ARE TO BE REPLACED WHERE FACES ARE ERODED TO DEPTHS GREATER THAN 10mm OR WHERE EXTENSIVELY CRACKED/SHATTERED.
8. USE NEW REPLACEMENT F2 RATED BRICKS OF MATCHING SIZE, COLOUR AND TEXTURE. PROVIDE SAMPLES FOR CLIENT APPROVAL BEFORE ORDERING.
9. BRICKS ARE TO BE BEDDED IN NHL 3.5:SHARP SAND MORTAR IN 1:2.5 RATIO.
10. ALLOW TO REPLACE A PROVISIONAL QUANTITY OF 20No. BRICKS - TO BE ADJUSTED PRO RATA ON COMPLETION.



CHIMNEY STACK NO.3 (SOUTH & EAST SIDE)



CHIMNEY STACK NO.3 (EAST & NORTH SIDE)



CHIMNEY STACK NO.3 (WEST SIDE - PARTIAL VIEW)

NOT FOR CONSTRUCTION

Rev	Date	Description	Drawn	Check
T1	07.04.22	TENDER ISSUE	SW	SW

conisbee | Consulting Structural Engineers Consulting Civil Engineers
London • Cambridge • Norwich
1-5 Offord St London N1 1DH
Telephone 020 7700 6666
www.conisbee.co.uk

Drawing Status: FOR TENDER

Project: HORNIMAN MUSEUM HISTORIC FACADE & MASONRY REPAIRS

Title: CHIMNEY STACK REPAIR DETAILS

Drawing No: 211042-CON-XX-RF-DR-S-4002

Date: APR 2022
Scale: NTS
Drawn: SW
Engineer: SW
Project No: 211042
Revision: T1