

	and access path				
		Unit	Quantity	Rate	Price
A	Preliminaries				
A1	Third Party Insurance (Min £10,000,000) in line with Hyndburn Borough Council procurement policy requirements	Item	1		
A2	Insurance for the works	Item	1		
A3	Provision of welfare facilities on site for	Item	1		
A4	All works necessary in conjunction with the assumption of the role of Principal Contractor for the site in accordance with CDM Code of Practice.	Item	1		
A5	Design resolution on site to resolve levels based on the provided information	Item	1		
A6	Reinstatement as required	Item	1		
B	Site clearance				
B1	Remove existing scrub from site to approved	m2	400		
B2	Break out existing pcc edgings including foundation to accommodate new footpath link	m3	0.5		
C	Excavation and Filling				
C1	Site strip topsoil to an average depth of 200mm and set material aside for re-use	m ³	154		
C2	Cut and fill excavation using selected existing material to create level base for MUGA and perimeter access path deposited in layers no	m ³	154		
C3	Double handling of topsoil previously set aside and grading to bankings and gradients around perimeter of the works allow for raking and	Item	1		
C4	Excavate to an average depth of 300mm for 150mm x 50mm PCC edgings to perimeter of ball court, along perimeter of ball court access path	m ³	5		
C5	Excavate interceptor trench on south and east edge of ball court, 1.0m wide to an average depth of 600mm ensuring base of trench falls away	m ³	34		
D	Filling				
D1	Provide and lay MOT type 1 limestone sub base to ball court and path areas to an average depth	m3	116		
D2	Provide and lay 50mm clean limestone to prepared cut-off trench to an average depth of	m3	25		
E	Roads and Paving				
E1	10mm nominal size porous Bitumen Macadam surface course 30mm depth 125 pen to BS 4987	m2	770		
E2	20mm nominal size open textured Bitumen Macadam binder course to MUGA court area	m2	770		
E3	Provide and lay to line and level 50mm x 150mm PCC edgings, including bed and haunch with C20P	lin m.	170		
E4	Allowance for return visit to lay surface course on completion of installation of ball court posts	Item	1		

F	Gate				
F1	Supply and install a prosafe gate in Hot Dip Galvanised finish to BS EN ISO 1461 as per manufacturers installation drawing. Allow for cutting a gap in the existing play area railing to	Item	1		
G	Seeding				
G1	soiled areas and apply low maintenance grass seed mix to prepared surface at a rate of 50g per square metre (Provisional QTY)	m ²	700		
H1	Contractors own item	Item	1		
		Sub-Total			
		5 % Contingency			
		Total			