



Adjacent properties and boundaries are shown for illustrative purposes only and have not been surveyed unless otherwise stated. Do not scale from this drawing except for planning consent purposes.

NOTES:

- All cutting, drilling & profiling of yorkstone to be
- undertaken off site; • Accuracy of level surface + or - 10 mm from datum;
- Setting out to be confirmed & agreed on site in advance of works;
- Stone colour to be agreed on site with samples provided by manufacturers;
- Drawings based on information supplied by client.
- Assumed accuracy, contractor to check on site. Contractor to note that the building will remain fully
- operational during the works. Access & crossover with public in abeyance.
- Contractor to refer to Planning Consent no. PP/19/05009 for working time & other restrictions/conditions Client to provide access to the toilet to contractors.

Contractor to investigate all on site drainage including location, invert levels & flow directions & report to engineer.

GENERAL NOTES

For all structural elements refer to engineer's drawings. Do not scale from this drawing.

Reinforced Concrete Plinth

For all structural elements refer to Ward Morgan Ltd. drawings.

For all aspects of underground drainage design, refer to clients record & drawings.

General Notes:

All products, materials and fittings to be installed to primary manufacturer's instructions, relevant regulations, standards and guidance. Contractor to ensure compatibility of all products used on site.

Materials should comply with appropriate British Standards or Agrément Certificates. The materials should be marked, stamped, independently certified or otherwise justified by test or calculation to show their suitability. Materials should be in accordance with BS8000 series of documents and other

accepted good practice (eg. Quality assured to ISO 9000).

Contractor is responsible for identifying all service routes at tender stage and allowing for re-routing as required.

Contractor is responsible to obtain all required consents and licences for connections to services and highways alterations / work.

Contractor to provide samples of all finishes and materials to client for approval in advance of ordering including masonry, pointing, and sample panels.

See Planning Consent for detailed requirements and Conditions generally.

See separate specification doc.

70mm yorkstone
Steintec tuffbe

Revisions



B 22/11/2019

Chaplin Farrant

Bank Chambers 69 High Street Winchester Hampshire SO23 9DA

Tel: 01962 862234 Fax: 01962 840506

www.cfw-architects.com

Also at: Norwich London

This drawing is copyright of the Architects and shall not be reproduced without their permission.

Check all dimensions and report any errors or omissions.

Tender

 17/12/2019
 Drainage shown, anti-skate details, sheffield cycle stands removed, general updates
 SS

reference to separate spec.

meeting with engineer.

DESCRIPTION

Updates to engineers comments &

Notes added. General updates fallowing

National Army Museum

Tank Plinth, The National Army Museum, Chelsea PROJECT

PD

PD

PD

DRAWN CHECKED

SS

SS

Proposed Plans, Elevations, email: studio@cfw-architects.com Sections & Details

19137w	
PROJECT REF:	

AP100	С
DRAWING NO:	REVISION
05/11/2019	As shown @A1
DATE	SCALE
SS	PD
DRAWN BY	CHECKED BY