

PRELIMINARIES					
Measurements in these schedules have been measured from the AutoCAD base drawing. They					
Item	Description	Qty	Unit	Rate	Total
1	<b>Health and Safety:</b> Allow for all provisions to comply with Health and Safety legislation.	1	Item		
2	<b>Paying Licences:</b> Include the paying of all necessary licences and fees in connection with this item.	1	Item		
3	<b>Management of works:</b> Programme of the works including revisions through the life of the contract as requested by the CA.	1	Item		
4	<b>Establish the Site:</b> Allow for all materials and operations to establish the site including water supply where required	1	Item		
5	<b>Run Site:</b> Allow for all materials and operations to run site and to comply with the clauses of the preliminaries	1	Item		
6	<b>Service Detection:</b> Allow for the locating of services on site prior to work commencing.	1	Item		
7	<b>Setting out:</b> Allow for setting out the works and confirming with the CA	1	Item		
8	<b>Ground protection:</b> Allow for the protection of surfacing outside of the site. Make provision for delivery and plant vehicles to unload/ work causing minimal damage.	1	Item		
9	<b>Temporary fencing:</b> Provide, erect and maintain HERAS or equivalent, fencing to the site. Fencing is to protect the site and public during the construction period until the site is to be opened to the public. Remove on completion of the works.	1	Item		
10	<b>Mud:</b> Allow for regular clearance of mud and debris from footpaths to keep access safe at all times through the works.	1	Item		
11	<b>Compaction:</b> Control access routes to avoid compaction as far as possible, all compacted soil to be broken up before practical completion	1	Item		

12	<b>Access route:</b> Allow for a temporary barrier for out of hours times. Making good any areas where vehicles have accessed the site and from storage/ compound and parking places at the end of the works.	1	Item		
13	<b>Removal off site:</b> Allow for all materials and operations to complete works on site, and remove compound and make good all areas of working.	1	Item		
14	<b>Omitted Work:</b> The Tenderer is to describe in full and price any item of the works that is not provided for in the Schedules and for which payment will be required.	1	Item		
<b>To collection</b>					

Measurements in these schedules have been measured from the AutoCAD base drawing. They should be					
Item	Description	Qty	Unit	Rate	Total
1.1	PRELIMINARIES as detailed in Schedule A	1	no		
1.2	ROSPA post installation inspection and accompanying report	1	Item		
<b>2 CLEARANCE AND EARTHWORKS</b>					
2.1	Excavate to formation and prepare area for installation of new play equipment and associated surfacing (basket swing, trampoline, cableway)	3	items		
2.2	Excavate to formation and prepare area for installation of new gym equipment and associated surfacing (Caloo 8 piece community bundle)	8	items		
2.3	Excavate to formation and prepare area for installation of sports equipment and associated surfacing (two football goals, basketball hoop and backboard)	3	items		
2.4	Excavate to formation and prepare area for installation of hard surfacing on half basketball court	188	m2		
2.5	Create 2 shallow depressions 500 mm deep centres	30	m2		
2.6	Existing footpath - break out and remove existing footpath with all subbase, edgings and foundations. Allow for reuse of suitable arisings in sub base of new footpath. Make up soil to marry in with existing levels.	18	lm		
2.7	Excavate to formation and prepare area for installation of 1.2m wide Breedon gravel path inset with sleepers as shown on plan with a Filcris flexible edging	33	lm		
2.8	Excavate to formation and prepare area for installation of 1.2m wide Breedon gravel path with a Filcris flexible edging	7	lm		
2.9	Remove gate and adjacent fencing panels in bowtop fencing. Store until reinstalled, clean before installation. Report any issues with quality or function of product.	1	item		
3	Retain soil arisings for infilling excavations and mounding. Keep free of contamination and store in heaps <1m high	1	item		
3.1	Remove all stones larger than 60mm. concrete, brick, tile and other unwanted material to authorised tip	1	item		
<b>3 HARDWORKS</b>					
3.1	Supply and install 3 large items of play equipment (basket swing, trampoline, cableway)	3	items		
3.2	Supply and install 8 items of gym equipment (Caloo 8 piece community bundle)	8	items		
3.3	Supply and install 4 items of sports equipment (two football goals, basketballhoop and backboard)	4	items		
3.4	Supply and install tarmac surfacing with PC edging for basketball court	188	m2		

3.5	Marking of new basket ball court	1	item		
3.6	Safety surfacing: Supply and install Technix grass matting beneath new play equipment	3	items		
3.7	Safety surfacing: Supply and install Technix grass matting beneath new gym equipment	8	items		
3.8	Supply and install 1.2m wide Breedon gravel path inset with 44x 900mm sleepers at 750mm intervals and a Filcris flexible edging	33	lm		
3.9	Reinstall fencing and gate to new position	1	item		
<b>4 SOFTWORKS</b>					
4.1	Supply and sow grass seed to disturbed areas - Germinal seeds	1	item		
4.2	Supply and sow grass seed to disturbed areas - Emorsgate seeds (EM8 Meadow Mixture for Wetlands)	30	m2		
					<b>To collection</b>

**Acacia Street Play Area**

Measurements in these schedules have been measured from the AutoCAD base drawing. They should be checked on site prior to ordering materials.

Item	Description	Qty	Unit	Rate	Total
1.1	PRELIMINARIES as detailed in Schedule A	1	no		
1.2	ROSPA post installation inspection and accompanying report	1	Item		
Item	Description	Qty	Unit	GC Rate	GC Total
<b>2. CLEARANCE AND EARTHWORKS</b>					
2.1	Clearance: Remove 2 large items of play equipment for disposal, include foundations and surfacing and edging. (1x rotary unit and 1 x multiplay unit) Dispose of play surfacing	2	items		
2.2	Clearance: Remove 2 small item of play equipment for disposal, include foundations and surfacing and edging (2 springers) Dispose of play surfacing	2	items		
2.3	Clearance: Remove 1 large item (basket swing plus 2 flat swings). Store until reinstalled, clean before installation. Report any issues with quality or function of product. Dispose of play surfacing	1	item		
2.4	Clearance: Remove fencing and gate. Store until reinstalled, clean before installation. Report any issues with quality or function of product.	132	lm		
2.5	Retain soil arisings for infilling excavations and mounding. Keep free of contamination and store in heaps <1m high	1	item		
2.6	Remove all stones larger than 60mm. concrete, brick, tile and other unwanted material to authorised tip	1	item		
<b>3. HARDWORKS</b>					
3.1	Reinstall fence and gate to new playground position as identified on plan.	122	lm		
3.2	Reinstall retained large item of play equipment (basket swing plus two flat swings) and grass matting	1	item		
3.3	Supply and install 4 large items of play equipment (Bryncrug unit, surfboard, trampoline, cableway)	4	items		
3.4	Supply and install 8 items of gym equipment (Caloo 8 piece community bundle)	8	items		
3.5	Safety surfacing: Supply and install Technix grass matting beneath all play equipment	5	items		
3.6	Safety surfacing: Supply and install Technix grass matting beneath new gym equipment	8	items		
3.7	Supply and installation of 1.2m wide Breedon gravel path and a Filcris flexible edging	175	lm		
3.8	Installation of inset maze as per plan (single brick width path)	1600	lm		
<b>4. SOFTWORKS</b>					

4.1	Supply and sow grass seed to disturbed areas - Germinal seeds	1	item		
<b>To collection</b>					

<b>COLLECTION</b>			
SCHEDULE B: Ellenbrook	<b>£0.00</b>		
SCHEDULE C: Acacia	<b>£0.00</b>		
SUBTOTAL	<b>£0.00</b>		
<i>CONTINGENCIES 10%</i>	<b>£0.00</b>		
<b>TENDER TOTAL</b>	<b>£0.00</b>		